

Certification Test Report

Hearth & Home Technologies

Freestanding Pellet Stove

Model: CB1200

Prepared for: Hearth & Home Technologies
1445 North Highway
Colville, WA 99114

Prepared by: OMNI-Test Laboratories, Inc.
13327 NE Airport Way
Portland, OR 97230
(503) 643-3788

Test Period: 2/18/14 – 2/25/14

Report Date: March 2014

Report Number: 061-S-13-8.3

All data and information contained in this report are confidential and proprietary to Hearth & Home Technologies. Its significance is subject to the adequacy and representative character of the samples and to the comprehensiveness of the tests, examinations, or surveys made. The contents of this report cannot be copied or quoted, except in full, without specific, written authorization from Hearth & Home Technologies and OMNI-Test Laboratories, Inc. No use of the OMNI-Test Laboratories, Inc. name, logo, or registered mark (O-TL) is permitted, except as expressly authorized by OMNI-Test Laboratories, Inc. in writing.

TABLE OF CONTENTS


PREFACE.....		(3 pages)
1.	APPLIANCE DESCRIPTION/DRAWINGS.....	1-1 (199 pages)
	Appliance Description	1-3
	Manufacturer Design Drawings (K List)	1-4
	Manufacturer Design Drawings (Remainder).....	1-30
2.	QUALITY ASSURANCE/QUALITY CONTROL	2-1 (58 pages)
	Sample Analysis.....	2-3
	Calibrations – Methods 28 and 5G	2-23
	Example Calculations	2-48
3.	OWNER’S MANUAL.....	3-1 (49 pages)
4.	TEST DATA BY RUN.....	4-1 (26 pages)
	Run 1	4-3
	Run 2.....	4-9
	Run 3.....	4-15
	Run 4.....	4-21
5.	SAMPLING PROCEDURES AND TEST RESULTS	5-1 (7 pages)
	Introduction.....	5-2
	<u>Summary Tables</u>	
	Table 1.1 - Particulate Emissions Results.....	5-3
	Table 1.2 - Test Facility Conditions	5-3
	Table 1.3.1 - Fuel Measurements and Crib Descriptions - Pretest	5-4
	Table 1.3.2 - Fuel Measurements and Crib Descriptions - Test	5-4
	Table 1.4 - Dilution Tunnel Gas Measurements and Sampling Data	5-5
	Table 1.5 - Heater Operation	5-5
	Table 1.6 - Pretest Configurations	5-6
	Table 1.7 - Run Data.....	5-6
	Test Results and Discussion.....	5-7

AUTHORIZED SIGNATORIES


This report has been reviewed and approved by the following authorized signatories:



Chuck Burns, Accreditation & QA Manager
OMNI-Test Laboratories, Inc.



Jeremy Clark, Emissions Testing Manager
OMNI-Test Laboratories, Inc.



Aaron Kravitz, Technician
OMNI-Test Laboratories, Inc.




Model: CB1200
Hearth & Home Technologies
1445 North Highway
Colville, WA 99114

Hearth & Home Technologies

CB1200

Test Dates: 1/31/14-2/3/14



Hearth & Home Technologies CB1200

WOOD HEATER DESCRIPTION

Appliance Manufacturer: Hearth & Home Technologies

Wood Stove Model: CB1200

Type: Freestanding, convective-type pellet room heater

PELLET HEATER INFORMATION

Materials of Construction: The unit is constructed primarily of mild steel. The feed door has three glass panels, one 14" by 11", and the other two 4" by 11", and 3/4" rope gasket.

Air Introduction System: Air enters the firebox through the firepot via a combustion fan.

Combustion Control Mechanisms: Electronically controlled via a toggle switch on the side of the stove.

Combustor: N/A.

Internal Baffles: N/A

Other Features: N/A

Flue Outlet: The 3" diameter flue outlet is located in the rear of the unit.

WOOD HEATER OPERATING INSTRUCTIONS

Specific Written Instructions: See Section 3 of this report. All markings and instruction materials were reviewed for content prior to printing.

Model: CB1200
Hearth & Home Technologies
1445 North Highway
Colville, WA 99114

Run 1

Wood Heater Test Data - EPA Method 5G

Manufacturer: Hearth & Home
 Model: CB 1200
 Project No.: 061-S-13-8.3
 Tracking No.: 1931
 Run: 1
 Test Date: 02/18/14

Burn Rate	2.56 kg/hr dry
Average Tunnel Temperature	119 degrees Fahrenheit
Average Gas Velocity in Dilution Tunnel - vs	12.7 feet/second
Average Gas Flow Rate in Dilution Tunnel - Qsd	7849.2 dscf/hour
Average Delta p	0.033 inches H2O
Average Delta H	1.53 inches H2O
Total Time of Test	120 minutes

	AVERAGE	SAMPLE TRAIN 1	SAMPLE TRAIN 2
Total Sample Volume - Vm	16.18 cubic feet	16.16 cubic feet	16.20 cubic feet
Average Gas Meter Temperature	67 degrees Fahrenheit	67 degrees Fahrenheit	68 degrees Fahrenheit
Total Sample Volume (Standard Conditions) - Vmstd	16.2 dscf	16.3 dscf	16.2 dscf
Total Particulates - mn		2 mg	2 mg
Particulate Concentration (dry-standard)	0.00012 grams/dscf	0.00012 grams/dscf	0.00012 grams/dscf
Particulate Emission Rate	0.97 grams/hour	0.97 grams/hour	0.97 grams/hour
Adjusted Emissions	1.77 grams/hour	1.77 grams/hour	1.77 grams/hour
Difference from Average		0.00 grams/hour	0.00 grams/hour
7.5% of the average emission rate	0.13		
Weighted Average Emission Rate Limit	4.10 grams/hour		
7.5% of the weighted average emission rate limit	0.31		
Results Are Acceptable			

Wood Heater Test Data - EPA Method 5G

Run: 1
 Manufacturer: Hearth & Home
 Model: CB 1200
 Tracking No.: 1931
 Project No.: 061-S-13-8.3
 Test Date: 18-Feb-14
 Beginning Clock Time: 11:25
 Recording Interval: 10 min.
 Total Sampling Time: 120 min.

Velocity Traverse Data								
	Pt.1	Pt.2	Pt.3	Pt.4	Pt.5	Pt.6	Pt.7	Pt.8
Initial dP	0.030	0.036	0.038	0.032	0.034	0.022	0.038	0.036
Initial Temp.	116	116	116	116	116	116	116	116

OMNI Equipment Numbers: 23, 128, 131, 132, 209, 282, 283B, 288, 343, 371, 372, 378, 410

PM Control Module: 371/372
 Dilution Tunnel MW(dry): 29.00 lb/lb-mole
 Dilution Tunnel MW(wet): 28.56 lb/lb-mole
 Dilution Tunnel H2O: 4.00 percent
 Dilution Tunnel Static: -0.420 "H2O
 Pitot Tube Cp: 0.99
 Meter Box Y Factor: 1.002 (1) 0.999 (2)
 Barometric Pressure: 29.91 29.86 29.82 Average

Signature/Date: [Signature] 3/17/14
 Tunnel Velocity: 12.72 ft/sec.
 Initial Tunnel Flow: 130.7 scfm
 Average Tunnel Flow: 130.8 scfm
 Tunnel Area: 0.1963 ft²
 Post-Test Leak Check (1): 0.014 cfm@"Hg
 Post-Test Leak Check (2): 0.001 cfm@"Hg
 Fuel Moisture (dry basis %): 6.31
 Total Particulate (1): 2.0
 Total Particulate (2): 2.0

Elapsed Time	Particulate Sampling Data														Fuel Weight, lb		Wood Heater Temperature Data, oF														Stack
	Gas Meter Cubic Feet (1)	Gas Meter Cubic Feet (2)	Sample Rate, cfm (1)	Sample Rate, cfm (2)	Orifice dH (1)	Orifice dH (2)	Meter oF (1)	Meter oF (2)	Meter Vac. In. Hg. (1)	Meter Vac. In. Hg. (2)	Dilution Tunnel Temp.	Dilution Tunnel dP	Pro. Rate (10%) (1)	Pro. Rate (10%) (2)	Scale Reading	Weight Change	Firebox Top	Firebox Bottom	Firebox Back	Firebox Left	Firebox Right	Catalyst Exit	Average Surface	Stack	Filter (1)	Filter (2)	Impinger exit (1)	Impinger exit (2)	Ambient	Draft In. H2O	
0	0.000	0.000			0.70	0.70	66	67	0.67	0.8	116	0.033			12.0		498	658	875	527	559	N/A	623.4	259	69	68	N/A	N/A	68	-0.075	
10	1.341	1.325	0.13	0.13	1.62	1.36	66	66	0.32	0.8	118	0.033	100	99	11.1	-0.9	570	648	841	509	554	N/A	624.4	257	72	73	N/A	N/A	68	-0.075	
20	2.684	2.656	0.13	0.13	1.61	1.36	65	66	0.33	0.8	117	0.033	101	99	10.1	-1	487	650	900	523	557	N/A	623.4	258	74	74	N/A	N/A	68	-0.074	
30	4.028	3.989	0.13	0.13	1.59	1.35	66	66	0.31	0.7	118	0.033	101	100	9.1	-1	493	659	904	523	566	N/A	629.0	262	75	75	N/A	N/A	69	-0.074	
40	5.376	5.322	0.13	0.13	1.61	1.34	66	67	0.32	0.7	118	0.033	101	100	8.2	-0.9	596	647	836	488	542	N/A	621.8	258	75	76	N/A	N/A	68	-0.073	
50	6.723	6.658	0.13	0.13	1.61	1.35	66	67	0.31	0.7	119	0.033	101	100	7.1	-1.1	517	663	791	522	568	N/A	612.2	262	75	76	N/A	N/A	69	-0.074	
60	8.071	7.994	0.13	0.13	1.60	1.35	67	68	0.31	0.7	119	0.033	101	100	6.1	-1	503	665	693	526	566	N/A	590.6	263	76	77	N/A	N/A	69	-0.074	
70	9.420	9.334	0.13	0.13	1.60	1.41	67	68	0.31	0.7	119	0.033	101	100	5.0	-1.1	510	674	670	539	585	N/A	595.6	265	76	77	N/A	N/A	69	-0.075	
80	10.768	10.707	0.13	0.14	1.60	1.41	67	68	0.31	0.7	120	0.033	101	103	4.1	-0.9	532	669	661	523	572	N/A	591.4	264	76	77	N/A	N/A	69	-0.074	
90	12.116	12.081	0.13	0.14	1.60	1.41	68	69	0.31	0.7	121	0.033	101	102	3.1	-1	564	671	647	540	573	N/A	599.0	265	77	78	N/A	N/A	69	-0.074	
100	13.464	13.455	0.13	0.14	1.59	1.40	68	69	0.31	0.7	119	0.033	101	102	2.1	-1	523	667	660	529	569	N/A	589.6	264	77	78	N/A	N/A	69	-0.074	
110	14.812	14.828	0.13	0.14	1.59	1.40	68	69	0.3	0.7	120	0.033	101	102	1.0	-1.1	558	671	662	541	576	N/A	601.6	265	77	78	N/A	N/A	70	-0.074	
120	16.160	16.202	0.13	0.14	1.59	1.41	68	69	0.31	0.7	120	0.033	101	102	0.0	-1	570	670	645	539	578	N/A	600.4	263	77	78	N/A	N/A	70	-0.074	
Avg/Total	16.160	16.202	0.13	0.14	1.53	1.33	66.77	67.62			118.77	0.033	100.78	100.78									23		75.08	75.77	N/A	N/A		-0.074	

Run Notes

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Run #: 1 Date: 2/18/14

Test Crew: A. Kowitz

OMNI Equipment ID #(s): 371, 372

PREBURN

DESCRIBE OR SKETCH AIR OR THERMOMSTAT SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 2
FRAP @ Full open
Toggle Switch @ High

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

PREBURN SETTINGS AND ACTIVITIES

TIME	AIR (THERMO) CHANGES PRIMARY/SECONDARY/TERTIARY	FAN SETTING CHANGE	ADD FUEL + WT.	ADD FUEL - WT.	RAKE COAL	COMMENT
39:00	_____	_____	11.9	_____	_____	_____

TEST

TEST FUEL CONFIGURATION SKETCH
(INDICATE VIEW ANGLE)

Pellets

START UP PROCEDURES

BYPASS: N/A

FUEL LOADING: N/A

DOOR: N/A

PRIMARY AIR: N/A

OTHER: N/A

DESCRIBE OR SKETCH TEST SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 2
Toggle Switch @ Full Open High
FRAP @ Full open

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

Technician signature:  Date: 2/18/14

Supplemental Data EPA 5G/5H

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Date: 2/18/14 Run #: 1 Booth: E2

Test Crew: A. Kravitz Start Time: 11:25 Stop Time: 13:35

OMNI Equipment #(s): 132, 209, 282, 284, 371, 372, 410, 417, 419, 378, 410

Stack Gas Leak Check:

Dilution Tunnel Gas Leak Check (5H only):

Initial: 0

Initial: N/A

Final: 0

Final: N/A

Calibrations: Span Gas CO₂: 16.75 O₂: 20.95 CO: 4.340 CO₂(DT): NA

Mid Gas CO₂: 10.02 O₂: 10.51 CO: 2.533 CO₂(DT): NA

f: .014
B: .001

Time			
O ₂	0.00	20.95	10.60
CO ₂	0.00	16.75	10.00
CO	0.000	4.340	2.534
CO ₂ (DT)	N/A		

Pre Test		
Zero	Span	Mid
10:50	10:51	10:52
0.00	20.95	10.60
0.00	16.75	10.00
0.000	4.340	2.534
N/A		

Post Test		
Zero	Span	Mid
1:58	1:58	1:58
0.03	20.92	10.61
0.05	16.68	9.97
0.000	4.300	2.513
N/A		

Air Velocity (ft/min): Initial: <50 Final: <50

Scale Audit (lbs): Initial: 10.0 Final: 10.0

Pitot Tube Leak Test: Initial: 0 Final: ✓

Stack Diameter (inches): 6

Induced Draft: 0

% Smoke Capture: 100

Flue Pipe Cleaned Prior to First Test in Series:

Date: 2/17 Initials: AK

	Initial	Middle	Ending
P _b (in/Hg)	29.91	29.86	29.82
Ambient (°F)	68	69	70

Tunnel Traverse	
dP (in H ₂ O)	T(°F)
.030	116
.036	
.038	
.032	
.022	
.034	
.038	
.036	
N/A	N/A
Static P:	- .42

Technician signature: [Signature]

Date: 2/18/14

Method 28 Preburn Data

Run Data											
Client:	Hearth & Home	Test Run:	1								
Model:	CB 1200	Date:	2/18/2014								
Project Number:	061-S-13-8.3	Test Crew:	A. Kravitz								
Tracking Number:	1931	Equipment:	288, 371, 372								
Coal Bed Range (lb):		N/A (pellet)									
Logged Data											
Temperatures (F)											
Elapsed Time (min)	Scale (lb)	Stack Draft (in H2O)	Stack	Ambient	FB Top	FB Bottom	FB Back	FB Left	FB Right	Cat. In	Cat. Out
0	25.2	-0.063	180	64	362	258	486	226	288		
10	24	-0.074	244	65	578	535	857	457	470		
20	22.9	-0.076	256	67	605	631	922	524	562		
30	21.9	-0.077	255	68	605	648	891	520	546		
40	33	-0.075	254	68	599	643	827	507	536		
50	31.9	-0.076	260	68	536	660	886	536	566		
60	30.9	-0.076	259	68	498	657	874	527	558		
Averages:			244.00	66.86	540.43	576.00	820.43	471.00	503.71		

A. Kravitz
2/28/14

Model: CB1200
Hearth & Home Technologies
1445 North Highway
Colville, WA 99114

Run 2

Wood Heater Test Data - EPA Method 5G

Manufacturer: Hearth & Home
 Model: CB 1200
 Project No.: 061-S-13-8.3
 Tracking No.: 1931
 Run: 2
 Test Date: 02/18/14

Burn Rate	1.47 kg/hr dry
Average Tunnel Temperature	102 degrees Fahrenheit
Average Gas Velocity in Dilution Tunnel - vs	12.5 feet/second
Average Gas Flow Rate in Dilution Tunnel - Qsd	7964.2 dscf/hour
Average Delta p	0.033 inches H2O
Average Delta H	1.76 inches H2O
Total Time of Test	120 minutes

	AVERAGE	SAMPLE TRAIN 1	SAMPLE TRAIN 2
Total Sample Volume - Vm	17.46 cubic feet	17.37 cubic feet	17.55 cubic feet
Average Gas Meter Temperature	67 degrees Fahrenheit	66 degrees Fahrenheit	68 degrees Fahrenheit
Total Sample Volume (Standard Conditions) - Vmstd	17.5 dscf	17.5 dscf	17.6 dscf
Total Particulates - mn		1.2 mg	1.1 mg
Particulate Concentration (dry-standard)	0.00007 grams/dscf	0.00007 grams/dscf	0.00006 grams/dscf
Particulate Emission Rate	0.52 grams/hour	0.55 grams/hour	0.50 grams/hour
Adjusted Emissions	1.06 grams/hour	1.10 grams/hour	1.02 grams/hour
Difference from Average		0.04 grams/hour	0.04 grams/hour
7.5% of the average emission rate	0.08		
Weighted Average Emission Rate Limit	4.10 grams/hour		
7.5% of the weighted average emission rate limit	0.31		
Results Are Acceptable			

Wood Heater Test Data - EPA Method 5G

Manufacturer: Hearth & Home
 Model: CB 1200
 Tracking No.: 1931
 Project No.: 061-S-13-8.3
 Test Date: 18-Feb-14
 Beginning Clock Time: 14:27
 Recording Interval: 10 min.
 Total Sampling Time: 120 min.

Velocity Traverse Data								
	Pt.1	Pt.2	Pt.3	Pt.4	Pt.5	Pt.6	Pt.7	Pt.8
Initial dP	0.030	0.036	0.038	0.032	0.034	0.022	0.038	0.036
Initial Temp.	116	116	116	116	116	116	116	116

OMNI Equipment Numbers: 23, 128, 131, 132, 209, 282, 283B, 288, 343, 371, 372, 378, 410

PM Control Module: 371/372
 Dilution Tunnel MW(dry): 29.00 lb/lb-mole
 Dilution Tunnel MW(wet): 28.56 lb/lb-mole
 Dilution Tunnel H2O: 4.00 percent
 Dilution Tunnel Static: -0.420 "H2O
 Pitot Tube Cp: 0.99
 Meter Box Y Factor: 1.002 (1) 0.999 (2)
 Barometric Pressure: Begin Middle End Average
29.82 29.85 29.88 29.85 "Hg

Signature/Date: [Signature] 3/17/14
 Tunnel Velocity: 12.54 ft/sec.
 Initial Tunnel Flow: 130.7 scfm
 Average Tunnel Flow: 132.7 scfm
 Tunnel Area: 0.1963 ft²
 Post-Test Leak Check (1): 0.005 cfm@"Hg
 Post-Test Leak Check (2): 0.002 cfm@"Hg
 Fuel Moisture (dry basis %): 6.31
 Total Particulate (1): 1.2
 Total Particulate (2): 1.1

Elapsed Time	Particulate Sampling Data														Fuel Weight, lb		Wood Heater Temperature Data, oF														Stack Draft In. H2O
	Gas Meter Cubic Feet (1)	Gas Meter Cubic Feet (2)	Sample Rate, cfm (1)	Sample Rate, cfm (2)	Orifice dH (1)	Orifice dH (2)	Meter oF (1)	Meter oF (2)	Meter Vac. In. Hg. (1)	Meter Vac. In. Hg. (2)	Dilution Tunnel Temp.	Dilution Tunnel dP	Pro. Rate (10%) (1)	Pro. Rate (10%) (2)	Scale Reading	Weight Change	Firebox Top	Firebox Bottom	Firebox Back	Firebox Left	Firebox Right	Catalyst Exit	Average Surface	Stack	Filter (1)	Filter (2)	Impinger exit (1)	Impinger exit (2)	Ambient		
0	0.000	0.000			0.70	0.70	68	69	0.76	0.8	116	0.033			6.9		477	528	542	383	424	N/A	470.8	217	71	71	N/A	N/A	69	-0.064	
10	1.445	1.458	0.14	0.15	1.86	1.61	68	69	0.16	0.7	104	0.033	100	100	6.3	-0.6	479	527	497	373	419	N/A	459.0	219	73	74	N/A	N/A	69	-0.064	
20	2.894	2.921	0.14	0.15	1.84	1.59	68	68	0.17	0.7	104	0.033	101	101	5.7	-0.6	482	533	519	379	430	N/A	468.6	219	74	75	N/A	N/A	69	-0.064	
30	4.337	4.380	0.14	0.15	1.84	1.59	67	68	0.16	0.7	104	0.033	100	101	5.0	-0.7	482	538	530	374	424	N/A	469.6	219	74	75	N/A	N/A	68	-0.065	
40	5.781	5.840	0.14	0.15	1.84	1.59	67	68	0.18	0.7	102	0.033	100	101	4.5	-0.5	465	523	524	369	417	N/A	459.6	216	74	75	N/A	N/A	68	-0.064	
50	7.228	7.302	0.14	0.15	1.84	1.58	67	68	0.16	0.7	101	0.033	101	101	3.9	-0.6	467	522	535	371	416	N/A	462.2	215	74	75	N/A	N/A	68	-0.064	
60	8.675	8.764	0.14	0.15	1.84	1.58	66	67	0.16	0.7	101	0.033	101	101	3.3	-0.6	452	513	535	355	403	N/A	451.6	213	74	74	N/A	N/A	68	-0.063	
70	10.124	10.227	0.14	0.15	1.84	1.60	66	67	0.17	0.7	102	0.033	101	101	2.6	-0.7	472	525	510	364	424	N/A	459.0	217	73	74	N/A	N/A	68	-0.064	
80	11.573	11.691	0.14	0.15	1.84	1.59	66	67	0.17	0.7	100	0.033	101	101	2.1	-0.5	428	493	564	341	385	N/A	442.2	207	73	74	N/A	N/A	68	-0.062	
90	13.023	13.156	0.15	0.15	1.85	1.59	65	67	0.17	0.7	99	0.033	101	101	1.6	-0.5	421	488	575	336	384	N/A	440.8	206	72	73	N/A	N/A	67	-0.063	
100	14.471	14.622	0.14	0.15	1.83	1.59	65	67	0.16	0.7	98	0.033	101	101	1.0	-0.6	406	472	487	330	374	N/A	413.8	202	72	73	N/A	N/A	67	-0.063	
110	15.923	16.088	0.15	0.15	1.85	1.60	65	67	0.18	0.7	97	0.033	101	101	0.6	-0.4	380	447	531	314	351	N/A	404.6	197	72	73	N/A	N/A	67	-0.061	
120	17.375	17.553	0.15	0.15	1.86	1.60	65	67	0.17	0.7	97	0.033	101	101	0.0	-0.6	426	469	444	313	378	N/A	406.0	202	72	72	N/A	N/A	67	-0.062	
Total	17.375	17.553	0.14	0.15	1.76	1.52	66.38	67.62			101.92	0.033	100.69	100.68									65		72.92	73.69	N/A	N/A		-0.063	

Run Notes

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Run #: 2

Date: 2/18/14

Test Crew: A. Kowitz

OMNI Equipment ID #(s): 371, 372

PREBURN

DESCRIBE OR SKETCH AIR OR THERMOMSTAT SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 2
FRAP @ Full open
Toggle Switch @ Low

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

PREBURN SETTINGS AND ACTIVITIES

TIME	AIR (THERMO) CHANGES PRIMARY/SECONDARY/TERTIARY	FAN SETTING CHANGE	ADD FUEL + WT.	ADD FUEL - WT.	RAKE COAL	COMMENT
	None					

TEST

TEST FUEL CONFIGURATION SKETCH
(INDICATE VIEW ANGLE)

Pellets

START UP PROCEDURES

BYPASS: N/A
 FUEL LOADING: N/A
 DOOR: N/A
 PRIMARY AIR: N/A

OTHER: N/A

DESCRIBE OR SKETCH TEST SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 2
Toggle Switch @ Low
FRAP @ Full open

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

Technician signature: *A. Kowitz*

Date: 2/18/14

Supplemental Data EPA 5G/5H

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Date: 2/18/14 Run #: 2 Booth: E2

Test Crew: A. Kravitz Start Time: 14:27 Stop Time: 16:27

OMNI Equipment #(s): 132, 209, 282, 284, 371, 372, 410, 417, 419

Stack Gas Leak Check:

Dilution Tunnel Gas Leak Check (5H only):

Initial: ∅

Initial: N/A

Final: ∅

Final: N/A

Calibrations: Span Gas CO₂: 16.75 O₂: 20.95 CO: 4.340 CO₂ (DT): NA

Mid Gas CO₂: 10.02 O₂: 10.51 CO: 2.533 CO₂ (DT): NA

f: .005
R: .002

Time
O ₂
CO ₂
CO
CO ₂ (DT)

Pre Test		
Zero	Span	Mid
1:58	1:54	1:55
0.00	20.92	10.61
0.005	16.68	9.97
0.000	4.306	2.513
NA		

Post Test		
Zero	Span	Mid
4:37	4:39	4:38
0.03	21.01	10.63
0.02	16.78	9.98
-0.003	4.339	2.521
NA		

Air Velocity (ft/min): Initial: 650 Final: 656

Scale Audit (lbs): Initial: 10.0 Final: 10.0

Pitot Tube Leak Test: Initial: ∅ Final: ∅

Stack Diameter (inches): 6

Induced Draft: ∅

% Smoke Capture: 100

Flue Pipe Cleaned Prior to First Test in Series:

Date: 2/17 Initials: AK

	Initial	Middle	Ending
P _b (in/Hg)	29.82	29.85	29.88
Ambient (°F)	64	68	67

Tunnel Traverse		
dP (in H ₂ O)	T(°F)	
.030	116	
.036	↓	
.038		
.032		
.022		
.034		
.038		
.036		
NA		NA
Static P:		-.42

Technician signature: 

Date: 2/18/14

Method 28 Preburn Data

Run Data	
Client: <u>Hearth & Home</u>	Test Run: <u>2</u>
Model: <u>CB 1200</u>	Date: <u>2/18/2014</u>
Project Number: <u>061-S-13-8.3</u>	Test Crew: <u>A. Kravitz</u>
Tracking Number: <u>1931</u>	Equipment: <u>288, 371, 372</u>
Coal Bed Range (lb): <u>N/A (pellet)</u>	

		Temperatures (F)									
		Stack	Ambient	FB Top	FB Bottom	FB Back	FB Left	FB Right	Cat. In	Cat. Out	
Elapsed Time (min)	Scale (lb)	Stack Draft (in H2O)	264	70	569	670	664	542	578		
10	18.1	-0.068	235	69	535	600	563	442	482		
20	17.6	-0.065	223	70	493	553	590	403	437		
30	16.9	-0.066	223	69	489	548	525	396	443		
40	16.3	-0.063	214	69	461	517	575	373	406		
50	15.7	-0.065	219	69	485	532	531	380	421		
60	15.1	-0.065	217	69	477	529	540	382	423		
Averages:		-0.067	227.86	69.29	501.29	564.14	569.71	416.86	455.71		

Akr
2/28/14

Model: CB1200
Hearth & Home Technologies
1445 North Highway
Colville, WA 99114

Run 3

Wood Heater Test Data - EPA Method 5G

Manufacturer: Hearth & Home
 Model: CB 1200
 Project No.: 061-S-13-8.3
 Tracking No.: 1931
 Run: 3
 Test Date: 02/14/14

Burn Rate	0.92 kg/hr dry
Average Tunnel Temperature	92 degrees Fahrenheit
Average Gas Velocity in Dilution Tunnel - vs	12.4 feet/second
Average Gas Flow Rate in Dilution Tunnel - Qsd	8072.0 dscf/hour
Average Delta p	0.033 inches H2O
Average Delta H	1.79 inches H2O
Total Time of Test	120 minutes

	AVERAGE	SAMPLE TRAIN 1	SAMPLE TRAIN 2
Total Sample Volume - Vm	17.52 cubic feet	17.48 cubic feet	17.57 cubic feet
Average Gas Meter Temperature	67 degrees Fahrenheit	66 degrees Fahrenheit	67 degrees Fahrenheit
Total Sample Volume (Standard Conditions) - Vmstd	17.8 dscf	17.7 dscf	17.8 dscf
Total Particulates - mn		0.8 mg	0.7 mg
Particulate Concentration (dry-standard)	0.00004 grams/dscf	0.00005 grams/dscf	0.00004 grams/dscf
Particulate Emission Rate	0.34 grams/hour	0.36 grams/hour	0.32 grams/hour
Adjusted Emissions	0.74 grams/hour	0.79 grams/hour	0.70 grams/hour
Difference from Average		0.04 grams/hour	0.04 grams/hour
7.5% of the average emission rate	0.06		
Weighted Average Emission Rate Limit	4.10 grams/hour		
7.5% of the weighted average emission rate limit	0.31		

Results Are Acceptable

Wood Heater Test Data - EPA Method 5G

Run: 3
 Manufacturer: Hearth & Home
 Model: CB 1200
 Tracking No.: 1931
 Project No.: 061-S-13-8.3
 Test Date: 14-Feb-14
 Beginning Clock Time: 14:27
 Recording Interval: 10 min.
 Total Sampling Time: 120 min.

Velocity Traverse Data								
	Pt.1	Pt.2	Pt.3	Pt.4	Pt.5	Pt.6	Pt.7	Pt.8
Initial dP	0.026	0.032	0.040	0.034	0.036	0.028	0.036	0.034
Initial Temp.	94	94	94	94	94	94	94	94

OMNI Equipment Numbers: 23, 128, 131, 132, 209, 282, 283B, 288.343, 371, 372, 378, 410

PM Control Module: 371/372
 Dilution Tunnel MW(dry): 29.00 lb/lb-mole
 Dilution Tunnel MW(wet): 28.56 lb/lb-mole
 Dilution Tunnel H2O: 4.00 percent
 Dilution Tunnel Static: -0.410 "H2O
 Pitot Tube Cp: 0.99
 Meter Box Y Factor: 1.002 (1) 0.999 (2)
 Barometric Pressure: Begin Middle End Average
30.10 30.1 30.1 30.10 "Hg

Signature/Date: [Signature] 2/28/14
 Tunnel Velocity: 12.37 ft/sec.
 Initial Tunnel Flow: 134.0 scfm
 Average Tunnel Flow: 134.5 scfm
 Tunnel Area: 0.1963 ft²
 Post-Test Leak Check (1): 0.008 cfm@"Hg
 Post-Test Leak Check (2): 0.002 cfm@"Hg
 Fuel Moisture (dry basis %): 6.31
 Total Particulate (1): 0.8
 Total Particulate (2): 0.7

Elapsed Time	Particulate Sampling Data														Fuel Weight, lb		Wood Heater Temperature Data, oF														Stack Draft In. H2O
	Gas Meter Cubic Feet (1)	Gas Meter Cubic Feet (2)	Sample Rate, cfm (1)	Sample Rate, cfm (2)	Orifice dH (1)	Orifice dH (2)	Meter oF (1)	Meter oF (2)	Meter Vac. In. Hg. (1)	Meter Vac. In. Hg. (2)	Dilution Tunnel Temp.	Dilution Tunnel dP	Pro. Rate (10%) (1)	Pro. Rate (10%) (2)	Scale Reading	Weight Change	Firebox Top	Firebox Bottom	Firebox Back	Firebox Left	Firebox Right	Catalyst Exit	Average Surface	Stack	Filter (1)	Filter (2)	Impinger exit (1)	Impinger exit (2)	Ambient		
0	0.000	0.000	/	/	0.70	0.70	68	68	0.21	0.7	94	0.033	/	/	4.3	/	302	356	340	228	277	N/A	300.6	164	68	68	N/A	N/A	67	-0.053	
10	1.448	1.448	0.14	0.14	1.89	1.62	67	67	0.18	0.7	92	0.033	100	100	3.9	-0.4	302	355	348	231	282	N/A	303.6	167	70	70	N/A	N/A	67	-0.054	
20	2.901	2.906	0.15	0.15	1.88	1.60	66	67	0.17	0.7	92	0.033	101	100	3.5	-0.4	314	369	355	231	283	N/A	310.4	168	71	71	N/A	N/A	67	-0.054	
30	4.353	4.363	0.15	0.15	1.88	1.61	66	66	0.18	0.7	92	0.033	101	101	3.1	-0.4	309	361	349	233	282	N/A	306.8	168	71	71	N/A	N/A	67	-0.054	
40	5.802	5.823	0.14	0.15	1.88	1.60	66	67	0.17	0.7	92	0.033	100	101	2.8	-0.3	303	358	382	229	275	N/A	309.4	166	71	72	N/A	N/A	67	-0.054	
50	7.257	7.286	0.15	0.15	1.87	1.59	66	67	0.17	0.7	92	0.033	101	101	2.4	-0.4	290	347	390	225	270	N/A	304.4	165	71	72	N/A	N/A	66	-0.054	
60	8.713	8.752	0.15	0.15	1.89	1.59	67	67	0.18	0.7	91	0.033	101	101	2.1	-0.3	287	334	377	217	263	N/A	295.6	161	71	72	N/A	N/A	66	-0.052	
70	10.174	10.219	0.15	0.15	1.89	1.59	67	68	0.16	0.7	91	0.033	101	101	1.8	-0.3	285	336	378	215	261	N/A	295.0	161	71	72	N/A	N/A	66	-0.052	
80	11.634	11.686	0.15	0.15	1.89	1.61	67	68	0.18	0.7	91	0.033	101	101	1.4	-0.4	286	341	378	215	262	N/A	296.4	161	71	72	N/A	N/A	66	-0.052	
90	13.095	13.155	0.15	0.15	1.88	1.61	66	68	0.18	0.7	91	0.033	101	101	1.1	-0.3	282	329	386	219	259	N/A	295.0	161	71	71	N/A	N/A	66	-0.053	
100	14.557	14.626	0.15	0.15	1.87	1.61	66	67	0.17	0.7	92	0.033	101	101	0.6	-0.5	306	351	361	231	277	N/A	305.2	167	71	71	N/A	N/A	66	-0.054	
110	16.018	16.097	0.15	0.15	1.89	1.62	66	67	0.16	0.6	91	0.033	101	101	0.3	-0.3	289	347	385	224	262	N/A	301.4	163	71	71	N/A	N/A	66	-0.052	
120	17.479	17.568	0.15	0.15	1.87	1.60	66	67	0.17	0.7	90	0.033	101	101	0.0	-0.3	271	321	383	212	247	N/A	286.8	157	71	71	N/A	N/A	66	-0.051	
Avg/Total	17.479	17.568	0.15	0.15	1.79	1.53	66.46	67.23	/	/	91.62	0.033	100.77	100.76	/	/	/	/	/	/	/	/	14	/	70.69	71.08	N/A	N/A	/	-0.053	

Run Notes

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Run #: 3

Date: 2/24/14

Test Crew: A. Kowitz

OMNI Equipment ID #(s): 371, 372

PREBURN

DESCRIBE OR SKETCH AIR OR THERMOMSTAT SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 1
FRAP @ Low
Toggle Switch @ Low

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

PREBURN SETTINGS AND ACTIVITIES

TIME	AIR (THERMO) CHANGES PRIMARY/SECONDARY/TERTIARY	FAN SETTING CHANGE	ADD FUEL + WT.	ADD FUEL - WT.	RAKE COAL	COMMENT
	None					

TEST

TEST FUEL CONFIGURATION SKETCH
(INDICATE VIEW ANGLE)

Pellets

START UP PROCEDURES

BYPASS: N/A
 FUEL LOADING: N/A
 DOOR: N/A
 PRIMARY AIR: N/A
 OTHER: N/A

DESCRIBE OR SKETCH TEST SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 1
Toggle Switch @ Low
FRAP @ Low

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

Technician signature:

Date: 2/24/14

Supplemental Data EPA 5G/5H

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Date: 2/18/14

Run #: 3

Booth: E2

Test Crew: A. Kravitz

Start Time: 17:27

Stop Time: 16:27

OMNI Equipment #(s): 132, 209, 282, 288, 371, 372, 410, 417, 419

Stack Gas Leak Check:

Dilution Tunnel Gas Leak Check (5H only):

Initial: ∅

Initial: N/A

Final: ∅

Final: N/A

Calibrations: Span Gas CO₂: 16.75 O₂: 20.95 CO: 4.34 CO₂ (DT): N/A
Mid Gas CO₂: 10.02 O₂: 10.51 CO: 2.535 CO₂ (DT): N/A

A: .002
B: .002

Time	
O ₂	
CO ₂	
CO	
CO ₂ (DT)	

Pre Test		
Zero	Span	Mid
1:48	1:49	1:52
0.00	20.94	10.5
0.00	16.75	10.01
0.00	4.34	2.53
N/A		

Post Test		
Zero	Span	Mid
1630	1632	1631
0.02	20.92	10.58
0.02	16.77	10.01
-0.002	4344	2.528
N/A		

Air Velocity (ft/min): Initial: 450 Final: 450
Scale Audit (lbs): Initial: 10.0 Final: 10.0
Pitot Tube Leak Test: Initial: ∅ Final: ∅
Stack Diameter (inches): 6
Induced Draft: ∅
% Smoke Capture: 100
Flue Pipe Cleaned Prior to First Test in Series:
Date: 2/17 Initials: AK

	Initial	Middle	Ending
P _b (in/Hg)	30.10	30.10	30.10
Ambient (°F)	67	66	66

Tunnel Traverse	
dP (in H ₂ O)	T(°F)
.026	84
.032	↓
.040	
.034	
.028	
.036	
.036	
.034	
N/A	
N/A	
N/A	
Static P:	- .41

Technician signature: [Signature]

Date: 2/24/14

Method 28 Preburn Data

Run Data	
Client: <u>Hearth & Home</u>	Test Run: <u>3</u>
Model: <u>CB 1200</u>	Date: <u>2/24/2014</u>
Project Number: <u>061-S-13-8.3</u>	Test Crew: <u>A. Kravitz</u>
Tracking Number: <u>1931</u>	Equipment: <u>288, 371, 372</u>
Coal Bed Range (lb): <u>N/A (pellet)</u>	

Logged Data											
Elapsed Time (min)	Scale (lb)	Stack Draft (in H2O)	Stack	Temperatures (F)						Cat. In	Cat. Out
				Ambient	FB Top	FB Bottom	FB Back	FB Left	FB Right		
0	17.2	-0.034	91	64	102	102	154	83	105		
10	16.6	-0.052	154	63	281	260	315	159	227		
20	16.3	-0.05	152	64	274	310	331	186	238		
30	15.9	-0.05	154	65	269	321	351	199	251		
40	15.6	-0.05	156	66	276	327	357	208	253		
50	15.2	-0.053	164	66	297	354	327	222	276		
60	14.9	-0.053	164	67	302	356	340	228	277		
Averages:		-0.049	147.86	65.00	257.29	290.00	310.71	183.57	232.43		

AK

2/24/14

Model: CB1200
Hearth & Home Technologies
1445 North Highway
Colville, WA 99114

Run 4

Wood Heater Test Data - EPA Method 5G

Manufacturer: Hearth & Home
 Model: CB 1200
 Project No.: 061-S-13-8.3
 Tracking No.: 1931
 Run: 4
 Test Date: 02/25/14

Burn Rate	0.92 kg/hr dry
Average Tunnel Temperature	95 degrees Fahrenheit
Average Gas Velocity in Dilution Tunnel - vs	12.3 feet/second
Average Gas Flow Rate in Dilution Tunnel - Qsd	7992.7 dscf/hour
Average Delta p	0.033 inches H2O
Average Delta H	1.79 inches H2O
Total Time of Test	120 minutes

	AVERAGE	SAMPLE TRAIN 1	SAMPLE TRAIN 2
Total Sample Volume - Vm	17.58 cubic feet	17.48 cubic feet	17.68 cubic feet
Average Gas Meter Temperature	69 degrees Fahrenheit	68 degrees Fahrenheit	69 degrees Fahrenheit
Total Sample Volume (Standard Conditions) - Vmstd	17.8 dscf	17.7 dscf	17.8 dscf
Total Particulates - mn		0.9 mg	0.8 mg
Particulate Concentration (dry-standard)	0.00005 grams/dscf	0.00005 grams/dscf	0.00004 grams/dscf
Particulate Emission Rate	0.38 grams/hour	0.41 grams/hour	0.36 grams/hour
Adjusted Emissions	0.82 grams/hour	0.86 grams/hour	0.78 grams/hour
Difference from Average		0.04 grams/hour	0.04 grams/hour
7.5% of the average emission rate	0.06		
Weighted Average Emission Rate Limit	4.10 grams/hour		
7.5% of the weighted average emission rate limit	0.31		

Results Are Acceptable

Wood Heater Test Data - EPA Method 5G

Run: 4

Manufacturer: Hearth & Home
 Model: CB 1200
 Tracking No.: 1931
 Project No.: 061-S-13-8.3
 Test Date: 25-Feb-14
 Beginning Clock Time: 09:09
 Recording Interval: 10 min.
 Total Sampling Time: 120 min.

Velocity Traverse Data								
	Pt.1	Pt.2	Pt.3	Pt.4	Pt.5	Pt.6	Pt.7	Pt.8
Initial dP	0.024	0.032	0.040	0.032	0.034	0.022	0.040	0.038
Initial Temp.	94	94	94	94	94	94	94	94

OMNI Equipment Numbers: 23, 128, 131, 132, 209, 282, 283B, 288,343, 371, 372, 378, 410

PM Control Module: 371/372
 Dilution Tunnel MW(dry): 29.00 lb/lb-mole
 Dilution Tunnel MW(wet): 28.56 lb/lb-mole
 Dilution Tunnel H2O: 4.00 percent
 Dilution Tunnel Static: -0.410 "H2O
 Pitot Tube Cp: 0.99
 Meter Box Y Factor: 1.002 (1) 0.999 (2)
 Barometric Pressure: Begin Middle End Average
30.14 30.13 30.13 30.13 "Hg

Signature/Date: [Signature] 2/28/14
 Tunnel Velocity: 12.30 ft/sec.
 Initial Tunnel Flow: 132.6 scfm
 Average Tunnel Flow: 133.2 scfm
 Tunnel Area: 0.1963 ft²
 Post-Test Leak Check (1): 0.003 cfm@"Hg
 Post-Test Leak Check (2): 0.005 cfm@"Hg
 Fuel Moisture (dry basis %): 6.31
 Total Particulate (1): 0.9
 Total Particulate (2): 0.8

Elapsed Time	Particulate Sampling Data														Fuel Weight, lb		Wood Heater Temperature Data, oF														Stack Draft In. H2O
	Gas Meter Cubic Feet (1)	Gas Meter Cubic Feet (2)	Sample Rate, cfm (1)	Sample Rate, cfm (2)	Orifice dH (1)	Orifice dH (2)	Meter oF (1)	Meter oF (2)	Meter Vac. In. Hg. (1)	Meter Vac. In. Hg. (2)	Dilution Tunnel Temp.	Dilution Tunnel dP	Pro. Rate (10%) (1)	Pro. Rate (10%) (2)	Scale Reading	Weight Change	Firebox Top	Firebox Bottom	Firebox Back	Firebox Left	Firebox Right	Catalyst Exit	Average Surface	Stack	Filter (1)	Filter (2)	Impinger exit (1)	Impinger exit (2)	Ambient		
0	0.000	0.000			0.70	0.70	68	68	0.64	0.7	94	0.033			4.3		274	327	340	209	257	N/A	281.4	158	68	68	N/A	N/A	68	-0.050	
10	1.441	1.463	0.14	0.15	1.89	1.64	68	68	0.16	0.7	96	0.033	100	100	4.0	-0.3	284	335	349	214	263	N/A	289.0	160	70	71	N/A	N/A	68	-0.051	
20	2.893	2.932	0.15	0.15	1.88	1.63	67	68	0.16	0.7	97	0.033	101	101	3.6	-0.4	297	348	346	225	275	N/A	298.2	164	72	72	N/A	N/A	68	-0.051	
30	4.345	4.400	0.15	0.15	1.88	1.62	68	68	0.17	0.7	95	0.033	100	101	3.3	-0.3	274	322	370	212	255	N/A	286.6	158	72	73	N/A	N/A	68	-0.050	
40	5.798	5.869	0.15	0.15	1.88	1.62	68	69	0.17	0.7	96	0.033	101	101	2.9	-0.4	284	332	349	223	267	N/A	291.0	161	73	73	N/A	N/A	68	-0.051	
50	7.255	7.341	0.15	0.15	1.88	1.62	68	69	0.16	0.7	98	0.033	101	101	2.5	-0.4	310	355	352	233	284	N/A	306.8	169	73	74	N/A	N/A	68	-0.053	
60	8.712	8.815	0.15	0.15	1.87	1.62	69	70	0.17	0.7	96	0.033	101	101	2.1	-0.4	305	349	351	231	279	N/A	303.0	167	74	74	N/A	N/A	68	-0.052	
70	10.171	10.291	0.15	0.15	1.89	1.62	69	70	0.17	0.6	94	0.033	101	101	1.8	-0.3	287	338	370	226	267	N/A	297.6	164	74	74	N/A	N/A	68	-0.053	
80	11.630	11.768	0.15	0.15	1.88	1.62	69	70	0.17	0.6	94	0.033	101	101	1.5	-0.3	297	349	383	224	270	N/A	304.6	165	73	74	N/A	N/A	68	-0.053	
90	13.092	13.245	0.15	0.15	1.86	1.62	68	70	0.15	0.6	94	0.033	101	101	1.1	-0.4	296	346	387	233	279	N/A	308.2	168	73	73	N/A	N/A	68	-0.053	
100	14.552	14.723	0.15	0.15	1.89	1.62	68	69	0.16	0.6	93	0.033	101	101	0.7	-0.4	300	351	385	238	280	N/A	310.8	167	73	73	N/A	N/A	68	-0.054	
110	16.015	16.204	0.15	0.15	1.88	1.62	68	69	0.15	0.6	93	0.033	101	101	0.4	-0.3	299	348	386	234	276	N/A	308.6	166	73	73	N/A	N/A	67	-0.054	
120	17.477	17.683	0.15	0.15	1.88	1.63	67	69	0.16	0.6	92	0.033	101	101	0.0	-0.4	288	338	388	223	262	N/A	299.8	162	72	72	N/A	N/A	67	-0.052	
Avg/Total	17.477	17.683	0.15	0.15	1.79	1.55	68.08	69.00			94.77	0.033	100.77	100.76									18		72.31	72.62	N/A	N/A		-0.052	

Run Notes

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Run #: 4 Date: 2/25/14

Test Crew: A. Kowitz

OMNI Equipment ID #(s): 371, 372

PREBURN

DESCRIBE OR SKETCH AIR OR THERMOMSTAT SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 1
FRAP @ Low
Toggle Switch @ Low

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

PREBURN SETTINGS AND ACTIVITIES

TIME	AIR (THERMO) CHANGES PRIMARY/SECONDARY/TERTIARY	FAN SETTING CHANGE	ADD FUEL + WT.	ADD FUEL - WT.	RAKE COAL	COMMENT
	None					

TEST

TEST FUEL CONFIGURATION SKETCH
(INDICATE VIEW ANGLE)

Pellets

START UP PROCEDURES

BYPASS: N/A

FUEL LOADING: N/A

DOOR: N/A

PRIMARY AIR: N/A

OTHER: N/A

DESCRIBE OR SKETCH TEST SETTINGS BELOW:
(SETTINGS MUST BE ACCURATE AND REPRODUCIBLE)

PRIMARY:

Control Board @ 1
Toggle Switch @ Low
FRAP @ Low

SECONDARY: N/A

TERTIARY: N/A

FAN: Auto

Technician signature: Date: 2/25/14

Supplemental Data EPA 5G/5H

Client: Hearth & Home

Model: CB1200

Project #: 061-S-13-8.3

Tracking #: 1931

Date: 2/25/14

Run #: 4

Booth: E2

Test Crew: A. Kravitz

Start Time: 9:29

Stop Time: 11:09

OMNI Equipment #(s): 132, 209, 282, 284, 371, 372, 410, 411, 414

Stack Gas Leak Check:

Dilution Tunnel Gas Leak Check (5H only):

Initial: ∅

Initial: NA

Final: ∅

Final: NA

Calibrations: Span Gas CO₂: 16.75 O₂: 20.95 CO: 4.340 CO₂(DT): NA
Mid Gas CO₂: 10.02 O₂: 10.51 CO: 2.533 CO₂(DT): NA

A:003
B:005

Time
O ₂
CO ₂
CO
CO ₂ (DT)

Pre Test		
Zero	Span	Mid
0845	0846	0847
0.00	20.95	10.57
0.00	16.75	10.02
0.000	4.340	2.535
NA		

Post Test		
Zero	Span	Mid
1113	1115	1116
0.03	20.84	10.58
0.03	16.73	10.03
-0.001	4.322	2.524
NA		

Air Velocity (ft/min): Initial: 450 Final: 450

Scale Audit (lbs): Initial: 10.0 Final: 10.0

Pitot Tube Leak Test: Initial: ∅ Final: ∅

Stack Diameter (inches): 6

Induced Draft: ∅

% Smoke Capture: 100

Flue Pipe Cleaned Prior to First Test in Series:

Date: 2/17 Initials: AK

	Initial	Middle	Ending
P _b (in/Hg)	30.14	30.17	30.13
Ambient (°F)	68	68	67

Tunnel Traverse		
dP (in H ₂ O)	T(°F)	
.024	49	
.032	↓	
.040		
.032		
.022		
.034		
.040		
.038		
NA		NA
Static P:	- .41	

Technician signature: AK

Date: 2/25/14

Method 28 Preburn Data

Run Data											
Client:	Hearth & Home	Test Run:									
Model:	CB 1200	Date:	4								
Project Number:	061-S-13-8.3	Test Crew:	A. Kravitz								
Tracking Number:	1931	Equipment:	288, 371, 372								
Coal Bed Range (lb):		N/A (pellet)									
Logged Data											
Temperatures (F)											
Elapsed Time (min)	Scale (lb)	Stack Draft (in H ₂ O)	Stack	Ambient	FB Top	FB Bottom	FB Back	FB Left	FB Right	Cat. In	Cat. Out
0	10.4	-0.026	79	66	81	88	104	73	83		
10	9.8	-0.049	147	67	262	227	282	144	209		
20	9.5	-0.05	155	67	275	303	320	182	244		
30	9.1	-0.05	155	67	271	321	336	197	252		
40	8.8	-0.049	154	68	268	323	301	202	248		
50	8.5	-0.05	157	67	278	325	352	205	254		
60	8.1	-0.051	158	68	274	327	342	209	256		
Averages:		-0.046	143.57	67.14	244.14	273.43	291.00	173.14	220.86		

AJK 2/28/14