Installation Manual
Installation and Appliance Setup

INSTALLER: Leave this manual with party responsible for use and operation.
OWNER: Retain this manual for future reference.


NOTICE: DO NOT discard this manual!

HEAT&GLO
No one builds a better fire

Models:

COSMO42-IFT
COSMO32-IFT

GAS-FIRED
c (UL) us
LISTED

This appliance may be installed as an OEM installation in manufactured home (USA only) or mobile home and must be installed in accordance with the manufacturer's instructions and the *Manufactured Home Construction and Safety Standard, Title 24 CFR, Part 3280* in the United States, or the *Standard for Installation in Mobile Homes, CAN/CSA Z240 MH Series,* in Canada.

This appliance is only for use with the type(s) of gas indicated on the rating plate. This appliance is not convertible for use with other gases, unless a certified kit is used.

In the Commonwealth of Massachusetts installation must be performed by a licensed plumber or gas fitter.

See Table of Contents for location of additional Commonwealth of Massachusetts requirements.

⚠ **WARNING:**
FIRE OR EXPLOSION HAZARD
Failure to follow safety warnings exactly could result in serious injury, death, or property damage.

- **DO NOT** store or use gasoline or other flammable vapors and liquids in the vicinity of this or any other appliance.

- **What to do if you smell gas**
  - **DO NOT** try to light any appliance.
  - **DO NOT** touch any electrical switch. **DO NOT** use any phone in your building.
  - Leave the building immediately.
  - Immediately call your gas supplier from a neighbor's phone. Follow the gas supplier's instructions.
  - If you cannot reach your gas supplier, call the fire department.

- Installation and service must be performed by a qualified installer, service agency, or the gas supplier.

⚠ **DANGER**

HOT GLASS WILL CAUSE BURNS.

DO NOT TOUCH GLASS UNTIL COOLED.

NEVER ALLOW CHILDREN TO TOUCH GLASS.

A barrier designed to reduce the risk of burns from the hot viewing glass is provided with this appliance and shall be installed for the protection of children and other at-risk individuals.

⚠ Safety Alert Key:

- *DANGER! Indicates a hazardous situation which, if not avoided <u>will</u> result in death or serious injury.*
- *WARNING! Indicates a hazardous situation which, if not avoided <u>could</u> result in death or serious injury.*
- *CAUTION! Indicates a hazardous situation which, if not avoided, could result in minor or moderate injury.*
- *NOTICE: Used to address practices not related to personal injury.*

Table of Contents

➜ = Contains updated information.

Installation Standard Work Checklist

ATTENTION INSTALLER:
Follow this Standard Work Checklist

This standard work checklist is to be used by the installer in conjunction with, not instead of, the instructions contained in this installation manual.

Customer: _____
Lot/Address: _____
_____
Model (circle one): COSMO42-IFT   COSMO32-IFT

Date Installed: _____
Location of Fireplace: _____
Installer: _____
Dealer/Distributor Phone # _____
Serial #: _____

⚠️ ***WARNING! Risk of Fire or Explosion!*** *Failure to install appliance according to these instructions could lead to a fire or explosion.*

	YES	IF NO, WHY?
Appliance Install		
Verified that the chase is insulated and sealed. (Pg. 15)	☐	_____
Required non-combustible board is installed. (Pg. 37)	☐	_____
Verified clearances to combustibles. (Pg. 13-14)	☐	_____
Fireplace is leveled and secured. (Pg. 36)	☐	_____
Venting/Chimney Section 7 (Pg 38-43)		
Venting configuration complies to vent diagrams.	☐	_____
Venting installed, locked and secured in place with proper clearance.	☐	_____
Firestops installed.	☐	_____
Attic insulation shield installed.	☐	_____
Exterior wall/Roof flashing installed and sealed.	☐	_____
Terminations installed and sealed.	☐	_____
Electrical Section 8 (Pg 44-48)		
Unswitched power (110-120 VAC) provided to the appliance.	☐	_____
Switch wires properly installed.	☐	_____
Gas Section 9 (Pg 49-51)		
Proper appliance for fuel type.	☐	_____
Was a conversion performed?	☐	_____
Leak check performed and inlet pressure verified.	☐	_____
Verified proper air shutter setting for installation type.	☐	_____
Finishing Section 10 (Pg 52-59)		
Combustible materials not installed in non-combustible areas.	☐	_____
Verified all clearances meet installation manual requirements.	☐	_____
Mantels and wall projections comply with installation manual requirements.	☐	_____
Appliance Setup Section 11 (Pg 60-62)		
All packaging and protective materials removed (inside & outside of appliance).	☐	_____
Media and optional logs, glass refractory and LED's installed correctly.	☐	_____
Glass assembly installed and secured.	☐	_____
Accessories installed properly.	☐	_____
Mesh, doors, or decorative front properly installed.	☐	_____
Manual bag and all of its contents are removed from inside/under the appliance and given to party responsible for use and operation.	☐	_____
Started appliance and verified no gas leaks exist.	☐	_____

Hearth & Home Technologies recommends the following:
• Photographing the installation and copying this checklist for your file.
• That this checklist remain visible at all times on the appliance until the installation is complete.

Comments: Further description of the issues, who is responsible (Installer/ Builder/ Other Trades, etc) and corrective action needed _____
_____

Comments Communicated to party responsible _____ by _____ on _____
                                      (Builder / Gen. Contractor/)   (Installer)   (Date)
➔ = Contains updated information.

2491-982 9/17

1 Product Specific and Important Safety Information

A. Appliance Certification

> *MODELS:* **COSMO42-IFT, COSMO32-IFT**
>
> *LABORATORY:* **Underwriters Laboratories, Inc. (UL)**
>
> *TYPE:* **Direct Vent Heater**
>
> *STANDARD:* **ANSI Z21.88-2017 • CSA 2.33-2017**

This product is listed to ANSI standards for "Vented Gas Fireplace Heaters" and applicable sections of "Gas Burning Heating Appliances for Manufactured Homes and Recreational Vehicles", and "Gas Fired Appliances for Use at High Altitudes".

NOTICE: This installation must conform with local codes. In the absence of local codes you must comply with the National Fuel Gas Code, ANSI Z223.1-latest edition in the U.S.A. and the CAN/CGA B149 Installation Codes in Canada.

> **NOT INTENDED FOR USE AS A PRIMARY HEAT SOURCE.**
> This appliance is tested and approved as either supplemental room heat or as a decorative appliance. It should not be factored as primary heat in residential heating calculations.

B. Glass Specifications

Hearth & Home Technologies appliances manufactured with tempered glass may be installed in hazardous locations such as bathtub enclosures as defined by the Consumer Product Safety Commission (CPSC). The tempered glass has been tested and certified to the requirements of **ANSI Z97.1** and **CPSC 16 CFR 1202** (Safety Glazing Certification Council **SGCC# 1595** and **1597**. Architectural Testing, Inc. Reports **02-31919.01** and **02-31917.01**).

This statement is in compliance with **CPSC 16 CFR Section 1201.5** "Certification and labeling requirements" which refers to **15** U.S. Code **(USC) 2063** stating "…Such certificate shall accompany the product or shall otherwise be furnished to any distributor or retailer to whom the product is delivered."

Some local building codes require the use of tempered glass with permanent marking in such locations. Glass meeting this requirement is available from the factory. Please contact your dealer or distributor to order.

C. BTU Specifications

Models (U.S. or Canada)		Maximum Input BTU/h	Minimum Input BTU/h	Orifice Size (DMS)
COSMO42-IFT (NG)	*(0-2000 FT)*	25,250	17,500	#42
COSMO42-IFT (PROPANE)	*(0-2000 FT*	23,500	17,500	.057
COSMO32-IFT (NG)	*(0-2000 FT)*	19,000	13,250	#45
COSMO32-IFT (PROPANE)	*(0-2000 FT)*	16,500	12,750	1.25 mm

D. High Altitude Installations

NOTICE: If the heating value of the gas has been reduced, these rules do not apply. Check with your local gas utility or authorities having jurisdiction.

When installing above 2000 feet elevation:

- In the USA: Reduce input rate 4% for each 1000 feet above 2000 feet.

- In CANADA: Input ratings are certified without a reduction of input rate for elevations up to 4500 feet (1370 m) above sea level. Please consult provincial and/or local authorities having jurisdiction for installations at elevations above 4500 feet (1370 m).

Check with your local gas utility to determine proper orifice size.

E. Non-Combustible Materials Specification

Material which will not ignite and burn. Such materials are those consisting entirely of steel, iron, brick, tile, concrete, slate, glass or plasters, or any combination thereof.

Materials that are reported as passing **ASTM E 136, Standard Test Method for Behavior of Materials in a Vertical Tube Furnace at 750 ºC** shall be considered non-combustible materials.

F. Combustible Materials Specification

Materials made of or surfaced with wood, compressed paper, plant fibers, plastics, or other material that can ignite and burn, whether flame proofed or not, or plastered or unplastered shall be considered combustible materials.

G. Electrical Codes

NOTICE: This appliance must be electrically wired and grounded in accordance with local codes or, in the absence of local codes, with **National Electric Code ANSI/NFPA 70-latest edition** *or the* **Canadian Electric Code CSA C22.1.**

• A 110-120 VAC circuit for this product must be protected with ground-fault circuit-interrupter protection, in compliance with the applicable electrical codes, when it is installed in locations such as in bathrooms or near sinks.

H. California

⚠ **WARNING:** This product and the fuels used to operate this product (liquid propane or natural gas), and the products of combustion of such fuels, can expose you to chemicals including benzene, which is known to the State of California to cause cancer and reproductive harm. For more information go to: www.P65Warnings.ca.gov.

I. Requirements for the Commonwealth of Massachusetts

For all side wall horizontally vented gas fueled equipment installed in every dwelling, building or structure used in whole or in part for residential purposes, including those owned or operated by the Commonwealth and where the side wall exhaust vent termination is less than seven (7) feet above finished grade in the area of the venting, including but not limited to decks and porches, the following requirements shall be satisfied:

Installation of Carbon Monoxide Detectors

At the time of installation of the side wall horizontal vented gas fueled equipment, the installing plumber or gas fitter shall observe that a hard wired carbon monoxide detector with an alarm and battery back-up is installed on the floor level where the gas equipment is to be installed. In addition, the installing plumber or gas fitter shall observe that a battery operated or hard wired carbon monoxide detector with an alarm is installed on each additional level of the dwelling, building or structure served by the side wall horizontal vented gas fueled equipment. It shall be the responsibility of the property owner to secure the services of qualified licensed professionals for the installation of hard wired carbon monoxide detectors.

In the event that the side wall horizontally vented gas fueled equipment is installed in a crawl space or an attic, the hard wired carbon monoxide detector with alarm and battery back-up may be installed on the next adjacent floor level.

In the event that the requirements of this subdivision can not be met at the time of completion of installation, the owner shall have a period of thirty (30) days to comply with the above requirements; provided, however, that during said thirty (30) day period, a battery operated carbon monoxide detector with an alarm shall be installed.

Approved Carbon Monoxide Detectors

Each carbon monoxide detector as required in accordance with the above provisions shall comply with NFPA 720 and be ANSI/UL 2034 listed and IAS certified.

Signage

A metal or plastic identification plate shall be permanently mounted to the exterior of the building at a minimum height of eight (8) feet above grade directly in line with the exhaust vent terminal for the horizontally vented gas fueled heating appliance or equipment. The sign shall read, in print size no less than one-half (1/2) in. in size, **"GAS VENT DIRECTLY BELOW. KEEP CLEAR OF ALL OBSTRUCTIONS".**

Inspection

The state or local gas inspector of the side wall horizontally vented gas fueled equipment shall not approve the installation unless, upon inspection, the inspector observes carbon monoxide detectors and signage installed in accordance with the provisions of 248 CMR 5.08(2)(a)1 through 4.

Exemptions

The following equipment is exempt from 248 CMR 5.08(2)(a)1 through 4:

- The equipment listed in Chapter 10 entitled "Equipment Not Required To Be Vented" in the most current edition of NFPA 54 as adopted by the Board; and

- Product Approved side wall horizontally vented gas fueled equipment installed in a room or structure separate from the dwelling, building or structure used in whole or in part for residential purposes.

MANUFACTURER REQUIREMENTS

Gas Equipment Venting System Provided

When the manufacturer of Product Approved side wall horizontally vented gas equipment provides a venting system design or venting system components with the equipment, the instructions provided by the manufacturer for installation of the equipment and the venting system shall include:

- Detailed instructions for the installation of the venting system design or the venting system components; and

- A complete parts list for the venting system design or venting system.

Gas Equipment Venting System <u>NOT</u> Provided

When the manufacturer of a Product Approved side wall horizontally vented gas fueled equipment does not provide the parts for venting the flue gases, but identifies "special venting systems", the following requirements shall be satisfied by the manufacturer:

- The referenced "special venting system" instructions shall be included with the appliance or equipment installation instructions; and

- The "special venting systems" shall be Product Approved by the Board, and the instructions for that system shall include a parts list and detailed installation instructions.

A copy of all installation instructions for all Product Approved side wall horizontally vented gas fueled equipment, all venting instructions, all parts lists for venting instructions, and/or all venting design instructions shall remain with the appliance or equipment at the completion of the installation.

See Gas Connection section for additional Commonwealth of Massachusetts requirements.

2 Getting Started

A. Design and Installation Considerations

Heat & Glo direct vent gas appliances are designed to operate with all combustion air siphoned from outside of the building and all exhaust gases expelled to the outside. No additional outside air source is required.

Installation MUST comply with local, regional, state and national codes and regulations. Consult insurance carrier, local building inspector, fire officials or authorities having jurisdiction over restrictions, installation inspection and permits.

<u>Before</u> installing, determine the following:

• Where the appliance is to be installed.

• The vent system configuration to be used.

• Gas supply piping requirements.

• Provisions for optional heat management system.

• Electrical wiring requirements.

• Framing and finishing details.

• Whether optional accessories—devices such as a fan, wall switch, LED lighting or remote control—are desired.

Installation and service of this appliance should be performed by qualified personnel. Hearth & Home Technologies recommends HHT Factory Trained or NFI certified professionals.

hearth**ED** FACTORY TRAINING *Fuel Your Fire*

NFI NATIONAL FIREPLACE INSTITUTE® A CERTIFICATION AGENCY

Improper installation, adjustment, alteration, service or maintenance can cause injury or property damage. For assistance or additional information, consult a qualified service technician, service agency or your dealer.

B. Good Faith Wall Surface

Figure 2.1 Good Faith Wall Surface Temperatures Above Appliance

If installing a television (TV) above the appliance, see Section 3 of the appliance Owner's Manual.

***NOTICE:** Temperatures listed above are taken with a temperature measuring probe as prescribed by the test standard used for appliance certification. Temperatures on walls or mantels taken with an infrared thermometer may yield increased temperatures of up to 30 degrees or more depending on the thermometer settings and material characteristics being measured. Use appropriate finishing materials that are able to withstand these conditions. For additional finishing guidelines, see Section 10.*

C. Tools and Supplies Needed

Before beginning the installation be sure that the following tools and building supplies are available.

Tape measure	Framing material
Pliers	Hammer
Phillips screwdriver	Manometer
Gloves	Framing square
Voltmeter	Flat blade screwdriver
Plumb line	Safety glasses
Level	Reciprocating saw

Electric drill and bits: (1/4 in./Phillips #2)

Non-corrosive leak check solution

1/2 - 3/4 in. length, #6 or #8 Self-drilling screws

Caulking material (300 ºF minimum continuous exposure rating)

D. Inspect Appliance and Components

• Carefully remove the appliance and components from the packaging.

• The vent system components and decorative fronts may be shipped in separate packages.

• If packaged separately, the log set and appliance grate must be installed.

• Report to your dealer any parts damaged in shipment, particularly the condition of the glass.

• **Read all of the instructions before starting the installation. Follow these instructions carefully during the installation to ensure maximum safety and benefit.**

WARNING! Risk of Fire or Explosion! Damaged parts could impair safe operation. DO NOT install damaged, incomplete or substitute components. Keep appliance dry.

Hearth & Home Technologies disclaims any responsibility for, and the warranty will be voided by, the following actions:

• Installation and use of any damaged appliance or vent system component.

• Modification of the appliance or vent system.

• Installation other than as instructed by Hearth & Home Technologies.

• Improper positioning of the gas logs or the glass door.

• Installation and/or use of any component part not approved by Hearth & Home Technologies.

Any such action may cause a fire hazard.

WARNING! Risk of Fire, Explosion or Electric Shock! DO NOT use this appliance if any part has been under water. Call a qualified service technician to inspect the appliance and to replace any part of the control system and/or gas control which has been under water.

3 Framing and Clearances

A. Appliance/Decorative Front Dimension Diagrams

Dimensions are actual appliance dimensions. Use for reference only. For framing dimensions and clearances refer to Section 5.

TOP VIEW

N Ø

HEAT MANAGEMENT SYSTEMS ACCESS (BOTH SIDES) Ø U

GAS LINE ACCESS

ELECTRICAL ACCESS

LEFT VIEW   **FRONT VIEW**   **RIGHT VIEW**

Appliance Dimensions Table

Location	Inches	Millimeters		Location	Inches	Millimeters
A	36	914		M	16-3/4	425
B	31	787		N	6-5/8	168
C	27-1/4	692		O	34-3/8	873
D	15-1/4	387		P	2-3/16	56
E	38-1/16	967		Q	6	152
F	3-1/2	89		R	17-1/4	438
G	7	178		S	25-7/8	657
H	41	1041		T	38-1/2	978
I	9-13/16	249		U	5	127
J	17-3/4	451		V	14	356
K	1/2	13		W	10-5/8	270
L	25-3/4	654		X	7-3/4	197

Figure 3.1 Appliance Dimensions - COSMO32-IFT

TOP VIEW

ØN

HEAT MANAGEMENT SYSTEMS ACCESS (BOTH SIDES)
Ø U

C

GAS LINE ACCESS

LEFT VIEW

FRONT VIEW

ELECTRICAL ACCESS

RIGHT VIEW

Appliance Dimensions Table

Location	Inches	Millimeters
A	48	1219
B	43	1092
C	39-1/16	993
D	15-1/4	387
E	33-11/16	856
F	3-1/2	89
G	7	178
H	46-1/2	1181
I	9-13/16	249
J	17-3/4	451
K	1/2	13
L	37-3/4	959

Location	Inches	Millimeters
M	16-3/4	425
N	6-5/8	168
O	32-3/8	822
P	2-3/16	56
Q	6	152
R	17-1/4	438
S	25-7/8	657
T	50-1/2	1283
U	5	127
V	14	356
W	10-5/8	270
X	7-3/4	197

Figure 3.2 Appliance Dimensions - COSMO42-IFT

CFT DECORATIVE FRONTS

Dimensions are actual decorative front dimensions. Use for reference only.

			A	B	C	D	E	F	G
COSMO32-IFT	CFT-32	in.	28-3/16	14-1/8	33-1/8	6-7/8	9-13/16	19-7/8	26-7/8
		mm	716	359	841	175	249	505	683
COSMO42-IFT	CFT-42	in.	40-3/16	14-1/8	45-1/8	6-7/8	9-13/16	19-7/8	26-7/8
		mm	1021	359	1146	175	249	505	683

Figure 3.3 Decorative Front Dimensions - CFT

MARTINI DECORATIVE FRONTS

			A	B	C	D	E	F	G
COSMO32-IFT	MAR-COSMO32	in.	28-1/4	14-7/8	34-3/16	6-5/16	9-3/8	20-3/4	27-1/8
		mm	718	377	867	160	239	527	689
COSMO42-IFT	MAR-COSMO42	in.	40-1/4	14-7/8	46-3/16	6-5/16	9-5/16	20-3/4	27-1/16
		mm	1023	377	1172	160	237	527	688

Figure 3.4 Decorative Front Dimensions - MARTINI

B. Clearances to Combustibles

When selecting a location for the appliance it is important to consider the required clearances to walls (see Figure 3.5).

WARNING! Risk of Fire or Burns! Provide adequate clearance around air openings and for service access. Due to high temperatures, the appliance should be located out of traffic and away from furniture and draperies.

NOTICE: Illustrations reflect typical installations and are FOR DESIGN PURPOSES ONLY. Illustrations/diagrams are not drawn to scale. Actual installation may vary due to individual design preference.

Figure 3.5 Appliance Locations

		A	B	C	D	E	F
COSMO32-IFT	Inches	44-5/8	37-5/8	63-1/8		15-1/16	17-1/4
	Millimeters	1134	956	1603	See Section 10.C for Alcove Installation.	383	438
COSMO42-IFT	Inches	50-1/2	49	71-1/2		19-1/2	17-1/4
	Millimeters	1283	1245	1816		495	438

Framing

This appliance is designed to be recessed into combustible framing with non-combustible material pre-installed on top and side. Drywall or combustible materials (minimum 1/2 inch thick) are designed to contact the non-combustible material/appliance as called out in Section 10 Finishing.

This appliance has been thoroughly tested to minimize drywall cracking and/or the protrusion of screws "screw pops" when framed as shown below.

Framing should be done in a manner similar to framing a window or door: Double-2x4/2x6 as a header for horizontal strength and utilizing Jack or Trimmer stud fastened to the King studs for vertical strength.

If elevating the appliance, the base of the unit should also be constructed in a similar manner to prevent settling.

Note: Refer to Section 10 for important information related to facing, drywall specifications and decorative front information.

Note: Header **MUST** be installed on end as shown in the diagram.

HEADER: TWO 2 X 4'S OR 2 X 6'S INSTALLED ON END

JACK (TRIMMER) STUD

KING STUD

MEASURE FROM TOP OF APPLIANCE OPENING

		MINIMUM FRAMING DIMENSIONS*									
Models		**A**	**B**	**C**	**D**	**E**	**F**	**G**	**H**	**I**	**J**
		Rough Opening (Vent Pipe)	Rough Opening (Height)	Rough Opening (Depth)	Rough Opening (Width)	Clearance to Ceiling	Combustible Floor	Combustible Flooring	Behind Appliance	Sides of Appliance	Front of Appliance
COSMO32-IFT	in.	8-5/8	36-1/2	17-3/4	37	31	0	0	1/2	1/2	36
	mm	219	927	451	940	787	0	0	13	13	914
COSMO42-IFT	in.	8-5/8	32-3/4	17-3/4	49	31	0	0	1/2	1/2	36
	mm	219	832	451	1245	787	0	0	13	13	914

* Adjust framing dimensions for interior sheathing (such as sheetrock)

Figure 3.6 Clearances to Combustibles

C. Constructing the Appliance Chase

A chase is a vertical box-like structure built to enclose the gas appliance and/or its vent system. In cooler climates the vent should be enclosed inside the chase.

NOTICE: Treatment of ceiling firestops and wall shield firestops and construction of the chase may vary with the type of building. These instructions are not substitutes for the requirements of local building codes. Therefore, you MUST check local building codes to determine the requirements to these steps.

Chases should be constructed and insulated in the same manner as the thermal envelope of the home based on the code requirements for that climate zone to prevent air leakage and draft problems. The chase is an extension of the building thermal envelope.

To further prevent drafts and air leakage, the wall shield and ceiling firestops should be caulked with caulk with a minimum of 300 °F continuous exposure rating to seal gaps. Gas line holes and other openings should be caulked with caulk with a minimum of 300 °F continuous exposure rating or stuffed with unfaced insulation. If the appliance is being installed on a cement surface, a layer of plywood may be placed underneath to prevent conducting cold up into the room.

*NOTICE: Install appliance on hard metal or wood surfaces extending full width and depth. **DO NOT** install directly on carpeting, vinyl, tile or any combustible material other than wood.*

NOTICE: When installing a sprinkler head in a fireplace chase, it is recommended to use a sprinkler head with a sprinkler activation temperature classified as Extra High. Keep sprinkler head away from vent and chimney.

WARNING! Risk of Fire! Maintain specified air space clearances to appliance and vent pipe:

• Insulation and other materials must be secured to prevent accidental contact.

• The chase must be properly blocked to prevent blown insulation or other combustibles from entering and making contact with fireplace or chimney.

• Failure to maintain airspace may cause overheating and a fire.

4 Termination Location and Vent Information

A. Vent Termination Minimum Clearances

⚠ **WARNING**

Fire Risk.

Maintain vent clearance to combustibles as specified.

• **DO NOT** pack air space with insulation or other materials.

Failure to keep insulation or other materials away from vent pipe could cause overheating and fire.

A	B
6 in. (minimum) up to 20 in. *152 mm/508 mm*	18 in. minimum *457 mm*
20 in. and over	0 in. minimum

Gas, Wood or Fuel Oil Termination Cap

B

A *

Gas Termination Cap **

* If using decorative cap cover(s), this distance may need to be increased. Refer to the installation instructions supplied with the decorative cap cover.

** In a staggered installation with both gas and wood or fuel oil terminations, the wood or fuel oil termination cap must be higher than the gas termination cap.

Figure 4.2 Staggered Termination Caps

HORIZONTAL OVERHANG

2 FT. MIN.

20 INCHES MIN.

VERTICAL WALL

LOWEST DISCHARGE OPENING

GAS DIRECT VENT TERMINATION CAP

X
12

ROOF PITCH IS X/ 12

H (MIN.) - MINIMUM HEIGHT FROM ROOF TO LOWEST DISCHARGE OPENING

Roof Pitch	H (Min.) Ft.
Flat to 6/12	1.0*
Over 6/12 to 7/12	1.25*
Over 7/12 to 8/12	1.5*
Over 8/12 to 9/12	2.0*
Over 9/12 to 10/12	2.5*
Over 10/12 to 11/12	3.25
Over 11/12 to 12/12	4.0
Over 12/12 to 14/12	5.0
Over 14/12 to 16/12	6.0
Over 16/12 to 18/12	7.0
Over 18/12 to 20/12	7.5
Over 20/12 to 21/12	8.0

* H minimum may vary depending on regional snowfall. Refer to local codes.

Figure 4.1 Minimum Height From Roof to Lowest Discharge Opening

B. Chimney Diagram

V	= VENT TERMINAL
(X)	= AIR SUPPLY INLET
▨	= AREA WHERE TERMINAL IS NOT PERMITTED

A = 12 inches.................clearances above grade, veranda, porch, deck or balcony

B = 9 inches (U.S.A.)

12 inches (Canada). clearance to window or door that may be opened, or to permanently closed window

C = 18 inches.................clearance below unventilated soffit

18 inches.................clearance below ventilated soffit

30 inches.................clearance below vinyl soffits and electrical service

D = 6 inches..................clearance to outside corner

E = 6 inches..................clearance to inside corner

F = 3 ft. (Canada)..........not to be installed above a gas meter/regulator assembly within 3 feet horizontally from the center-line of the regulator

G = 3 ft..........................clearance to gas service regulator vent outlet

H = 12 inches.................clearance to non-mechanical (unpowered) air supply inlet, combustion air inlet or direct-vent termination

i = 3 ft. (U.S.A.)
6 ft. (Canada)...........clearance to a mechanical (powered) air supply inlet

All mechanical air intakes within 10 feet of a termination cap must be a minimum of 3 feet below termination.

J = 7 ft. .... On **public** property: clearance above paved sidewalk or a paved driveway.

A vent shall not terminate directly above a sidewalk or paved driveway which is located between two single family dwellings and serves both dwellings.

K = 6 inches.................clearance from sides of electrical service

L = 12 inches................clearance above electrical service

Location of the vent termination must not interfere with access to the electrical service.

M = 18 inches ....clearance under veranda, porch, deck, balcony or overhang

42 inches ....vinyl or composite overhang

Permitted when veranda, porch, deck or balcony is fully open on a minimum of 2 sides beneath the floor.

Figure 4.3 Minimum Clearances for Termination

Covered Alcove Applications
(Spaces open only on one side and with an overhang)

N = 6 inches .... non-vinyl sidewalls

12 inches .... vinyl sidewalls

O = 18 inches .... non-vinyl soffit and overhang

42 inches .... vinyl soffit and overhang

P = 8 ft.

	Q$_{MIN}$	R$_{MAX}$
1 cap	3 feet	2 x Q$_{ACTUAL}$
2 caps	6 feet	1 x Q$_{ACTUAL}$
3 caps	9 feet	2/3 x Q$_{ACTUAL}$
4 caps	12 feet	1/2 x Q$_{ACTUAL}$

Q$_{MIN}$ = # termination caps x 3   R$_{MAX}$ = (2 / # termination caps) x Q$_{ACTUAL}$

Measure vertical clearances from this surface.

CLEARANCE = 6 IN.

Measure horizontal clearances from this surface.

CAUTION! Risk of Burns! Termination caps are HOT, consider proximity to doors, traffic areas or where people may pass or gather (sidewalk, deck, patio, etc.). Listed cap shields available. Contact your dealer.

- Local codes or regulations may require different clearances.
- Vent system termination is **NOT** permitted in screened porches.
- Vent system termination is permitted in porch areas with two or more sides open.
- Hearth & Home Technologies assumes no responsibility for the improper performance of the appliance when the venting system does not meet these requirements.
- Vinyl protection kits are suggested for use with vinyl siding.

C. Approved Pipe

Approved Pipe - Rigid

This appliance is approved for use with Hearth & Home Technologies SLP venting systems. Refer to Section 12.A for vent component information and dimensions.

DO NOT mix pipe, fittings or joining methods from different manufacturers.

The pipe is tested to be run inside an enclosed wall. There is no requirement for inspection openings at each joint within the wall.

WARNING! Risk of Fire or Asphyxiation. This appliance requires a separate vent. DO NOT vent to a pipe serving a separate solid fuel burning appliance.

Approved Pipe - Flex

This appliance is approved for use with Hearth & Home Technologies SLP-FLEX (6-5/8 inch) and SLP-FLEX7 (7 inch) venting systems.

DO NOT mix pipe, fittings or joining methods from different manufacturers. SLP-FLEX and SLP-FLEX7 venting cannot be interchanged.

SLP-FLEX (6-5/8 Inch): Venting may be used in any venting configuration shown in the venting tables provided that the horizontal vent length is reduced by 25%.

SLP-FLEX7 (7 Inch-Canada Only): Venting requires adapter collars to transition from the 6-5/8 IN. appliance starting collar and to the 6-5/8 IN. termination cap. Refer to installation instructions included with the SLP-FLEX7 collar adapter (SLP-FLEX7-A). SLP-FLEX7 Series venting is approved for use in Canada only.

The pipe is tested to be run inside an enclosed wall. There is no requirement for inspection openings at each joint within the wall.

WARNING! Risk of Fire or Asphyxiation. This appliance requires a separate vent. DO NOT vent to a pipe serving a separate solid fuel burning appliance.

D. Use of Elbows

Diagonal runs have both vertical and horizontal vent aspects when calculating the effects. Use the rise for the vertical aspect and the run for the horizontal aspect. See Figure 4.4.

Two 45º elbows may be used in place of one 90º elbow. On 45º runs, one foot of diagonal is equal to 8-1/2 in. (216 mm) horizontal run and 8-1/2 in. (216 mm) vertical run. A length of straight pipe is allowed between two 45º elbows. See Figure 4.4.

Figure 4.5 shows the vertical and horizontal offsets for SLP elbows.

SLP Pipe	Effective Length		Rise/Run	
	Inches	Millimeters	Inches	Millimeters
SLP4	4	102	2-3/4	70
SLP6	6	152	4-1/4	108
SLP12	12	305	8-1/2	216
SLP24	24	610	17	432
SLP36	36	914	25-1/2	648
SLP48	48	1219	34	864
SLP6A	3 to 6	76 to 152	2-1/8-4-1/4	54-108
SLP12A	3 to 12	76 to 305	2-1/8-8-1/2	54-216

Figure 4.4

Vent Type	X		Y	
	Inches	Millimeters	Inches	Millimeters
SLP	5	127	11-3/4	298

Vent Type	X	
	Inches	Millimeters
SLP	11-1/4	286

Figure 4.5 Vertical and Horizontal Offset for SLP Elbows

E. Measuring Standards

Vertical and horizontal measurements listed in the vent diagrams were made using the following standards:

- Pipe measurements are shown using the effective length of pipe. See Section 12.A (Figure 12.1) for information on effective length of pipe components.

- Horizontal terminations are measured to the outside mounting surface (flange of termination cap). See Figure 4.6.

- Vertical terminations are measured to top of last section of pipe. See Figure 4.7.

- Horizontal pipe installed level with no rise.

MEASURE TO SHADED SURFACE (OUTSIDE MOUNTING SURFACE)

Figure 4.6 Measure to Outside Mounting Surface

Figure 4.7 Measure to Top of Last Section of Pipe

F. Use of Flex Vent (SLP-FLEX Series 6-5/8 Inch)

The flex vent must be supported with the spacing between support intervals not exceeding 4 feet, with no more than 1/2 inch sag between supports.

A support is required at each change in venting direction, and in any location where it is necessary to maintain the necessary clearance to combustibles. A simple "up and out" installation (Figure 4.8) requires only enough support to maintain the necessary clearance to combustibles. However, the vent attachment point and the firestop location are considered to be supports.

Figure 4.8 Flex Vent Pipe - Generic Fireplace Shown

G. Vent Diagrams

General Rules:

- Elbows may be placed back to back anywhere in the system.

- Any 90º elbow may be replaced with two back to back 45º elbows.

- When penetrating a combustible wall, a wall shield firestop must be installed.

- When penetrating a combustible ceiling, a ceiling firestop must be installed.

- Horizontal runs of vent do not require vertical rise; horizontal runs may be level.

- Horizontal termination cap should have a 1/4 inch downward slant to allow any moisture in cap to be released. See Figure 4.9.


Figure 4.9 Vent Cap

Top Vent - Horizontal Termination

One 90º Elbow

Note: Use SLP Series components only.

Note: There <u>MUST</u> be a 25% reduction in total H when using SLP-FLEX Series (6-5/8 inch) vent except when using the simple up and out installation. See Figure 4.8.

V Minimum		H_1 Maximum			
		COSMO42-IFT		COSMO32-IFT	
90° Elbow		Not Allowed		1 ft.	305 mm
1 ft.	305 mm	1 ft.	305 mm	2 ft.	610 mm
2 ft.	610 mm	3 ft.	914 mm	4 ft.	1.2 m
3 ft.	914 mm	5 ft.	1.5 m	6 ft.	1.8 m
4 ft.	1.2 m	7 ft.	2.1 m	15 ft.	4.6 m
5 ft.	1.5	14 ft.	4.3 m		
		H MAX. =14 ft. (4.3 m) V + H MAX. = 40 ft. (12.2 m)		H MAX. =15 ft. (4.6 m) V + H MAX. = 40 ft. (12.2 m)	

CAUTION: The SLP-HRC-SS termination caps are not approved for use with these models. May lead to elevated glass temperature that may cause tempered glass breakage.

Figure 4.10

Top Vent - Horizontal Termination - (continued)

Two Elbows

Note: Use SLP Series components only.

Note: There MUST be a 25% reduction in total H when using SLP-FLEX Series (6-5/8 inch) vent except when using the simple up and out installation. See Figure 4.8.

V Minimum		H₁ + H₂ Maximum			
		COSMO42-IFT		COSMO32-IFT	
90° Elbow		Not Allowed		1 ft.	305 mm
1 ft.	305 mm	1 ft.	305 mm	2 ft.	610 mm
2 ft.	610 mm	2 ft.	610 mm	4 ft.	1.2 m
3 ft.	914 mm	4 ft.	1.2 m	6 ft.	1.8 m
4 ft.	1.2 m	6 ft.	1.8 m	15 ft.	4.6 m
5 ft.	1.5	15 ft.	4.6 m		
$H_1 + H_2$ MAX. =15 ft. (4.6 m) $V_1 + H_1 + H_2$ MAX. = 40 ft. (12.2 m)					

CAUTION: The SLP-HRC-SS termination caps are not approved for use with these models. May lead to elevated glass temperature that may cause tempered glass breakage.


H_2

H_1

V_1

INSTALLED HORIZONTALLY

Figure 4.11

Top Vent - Horizontal Termination - (continued)

Three Elbows

Note: There <u>MUST</u> be a 25% reduction in total H when using SLP-FLEX Series (6-5/8 inch) vent except when using the simple up and out installation. See Figure 4.8.

COSMO32-IFT					
V_1 **Minimum**		$H_1 + H_2$ **Maximum**		V_2	$V_1 + V_2$ **Minimum**
90° Elbow		6 ft.	1.8 m	*	*
1 ft.	305 mm	10 ft.	3.0 m	*	*
2 ft.	610 mm	12 ft.	3.7 m	*	*
3 ft.	914 mm	14 ft.	4.3 m	*	*
$H_1 + H_2$ MAX. =14 ft. (4.3 m) $V_1 + V_2 + H_1 + H_2$ MAX. = 40 ft. (12.2 m) *No specific restrictions on this value EXCEPT $V_1 + V_2 + H_1 + H_2$ cannot exceed 40 ft. (12.2 m)					

COSMO42-IFT					
V_1 **Minimum**		$H_1 + H_2$ **Maximum**		V_2	$V_1 + V_2$ **Minimum**
1 ft.	305 mm	6 ft.	1.8 m	*	*
2 ft.	610 mm	10 ft.	3.0 m	*	*
3 ft.	914 mm	12 ft.	3.7 m	*	*
4 ft.	1.2 m	14 ft.	4.3 m	*	*
$H_1 + H_2$ MAX. =14 ft. (4.3 m) $V_1 + V_2 + H_1 + H_2$ MAX. = 40 ft. (12.2 m) *No specific restrictions on this value EXCEPT $V_1 + V_2 + H_1 + H_2$ cannot exceed 40 ft. (12.2 m)					

CAUTION: The SLP-HRC-SS termination caps are not approved for use with these models. May lead to elevated glass temperature that may cause tempered glass breakage.

Figure 4.12

Top Vent - Horizontal Termination - (continued)

Three Elbows

⚠ **WARNING**
Risk of Fire!
This vent configuration can ONLY be used for COSMO42-IFT Natural Gas appliances.

V Minimum		$H_1 + H_2 + H_3$ MAXIMUM	
		COSMO42-IFT (NG ONLY)	
4 ft.	1.2 m	15 ft.	4.6 m
$H_1 + H_2 + H_3$ MAX. = 15 ft. (4.6 m) V_1 MAX. = 7 ft (2.1 m)			

Note: Use SLP Series components only.

Note: There MUST be a 25% reduction in total H when using SLP-FLEX Series (6-5/8 inch) vent except when using the simple up and out installation. See Figure 4.8.

CAUTION: The SLP-HRC-SS termination caps are not approved for use with these models. May lead to elevated glass temperature that may cause tempered glass breakage.

INSTALLED HORIZONTALLY

INSTALLED HORIZONTALLY

Figure 4.13

Top Vent - Vertical Termination

No Elbow

V$_1$ = 60 ft. Max. (18.3 m)

Note: Use SLP Series components only.

Note: If installing a vertical vent/termination off the top of the appliance, the optional vertical termination baffle may be needed.

V$_1$

Figure 4.14

Exhaust Restrictor Instructions

Exhaust restrictors are recommended for these vertically terminated products which have excessive draft. Exhaust restrictors will compensate for high draft, and restore visual flame height. If the vent configuration has a total vertical of 15-60 feet, an exhaust restrictor may be needed. The exhaust restrictor can be located in the appliance manual bag.

Exhaust Restrictor Installation

1. **COSMO42-IFT Only:** Remove inner heat shield by removing two wing nuts from top front of heat shield and two screws that secure the heat shield to back wall of fireplace. Retain heat shield and fasteners.

2. **COSMO32-IFT/COSMO42-IFT:** Center the exhaust restrictor in the open end of the exhaust outlet and secure through the slots on the exhaust restrictor with the two 1/4 in. self-tapping screws provided in the appliance manual bag. See Figure 4.15.

3. **COSMO42-IFT Only:** Reinstall shield by securing it with the two wing nuts and two screws previously removed in Step 1.

WING NUTS

SCREWS

HEAT SHIELD

EXHAUST RESTRICTOR

INSTALLED SCREWS

Figure 4.15 Installing Restrictor

Top Vent - Vertical Termination - (continued)

Two 90º Elbows

COSMO32-IFT					
V₁ Minimum		**H Maximum**		**V₂**	**V₁ + V₂ Minimum**
90° Elbow		2 ft.	610 mm	*	*
1 ft.	305 mm	3 ft.	914 mm	*	*
2 ft.	610 mm	5 ft.	1.5 m	*	*
3 ft.	914 mm	7 ft.	2.1 m	*	*
4 ft.	1.2 m	15 ft.	4.6 m	*	*
H MAX. =15 ft. (4.6 m) $V_1 + V_2$ + H MAX. = 40 ft. (12.2 m) * No specific restrictions on this value EXCEPT $V_1 + V_2$ + H cannot exceed 40 ft. (12.2 m)					

COSMO42-IFT					
V₁ Minimum		**H Maximum**		**V₂**	**V₁ + V₂ Minimum**
1 ft.	305 mm	2 ft.	610 mm	*	*
2 ft.	610 mm	3 ft.	914 mm	*	*
3 ft.	914 mm	5 ft.	1.5 m	*	*
4 ft.	1.2 m	7 ft.	2.1 m	*	*
5 ft.	1.5 m	15 ft.	4.6 m	*	*
H MAX. =15 ft. (4.6 m) $V_1 + V_2$ + H MAX. = 40 ft. (12.2 m) * No specific restrictions on this value EXCEPT $V_1 + V_2$ + H cannot exceed 40 ft. (12.2 m)					

Note: There <u>MUST</u> be a 25% reduction in total H when using SLP-FLEX Series (6-5/8 inch) vent except when using the simple up and out installation. See Figure 4.8.

Note: Use SLP Series components only.

Figure 4.16

Top Vent - Vertical Termination - (continued)

Three 90º Elbows

Note: Use SLP Series components only.

COSMO32-IFT					
V_1 Minimum		$H_1 + H_2$ Maximum		V_2	$V_1 + V_2$ Minimum
90° Elbow		1 ft.	305 mm	*	*
1 ft.	305 mm	2 ft.	610 mm	*	*
2 ft.	610 mm	4 ft.	1.2 m	*	*
3 ft.	914 mm	6 ft.	1.8 m	*	*
4 ft.	1.2 m	14 ft.	4.3 m	*	*
H MAX. =14 ft. (4.3 m) $V_1 + V_2 + H_1 + H_2$ MAX. = 40 ft. (12.2 m) * No specific restrictions on this value EXCEPT $V_1 + V_2 + H_1 + H_2$ cannot exceed 40 ft. (12.2 m)					

COSMO42-IFT					
V_1 Minimum		$H_1 + H_2$ Maximum		V_2	$V_1 + V_2$ Minimum
1 ft.	305 mm	1 ft.	305 mm	*	*
2 ft.	610 mm	2 ft.	610 mm	*	*
3 ft.	914 mm	4 ft.	1.2 m	*	*
4 ft.	1.2 m	6 ft.	1.8 m	*	*
5 ft.	1.5 m	14 ft.	4.3 m	*	*
H MAX. =14 ft. (4.3 m) $V_1 + V_2 + H_1 + H_2$ MAX. = 40 ft. (12.2 m) * No specific restrictions on this value EXCEPT $V_1 + V_2 + H_1 + H_2$ cannot exceed 40 ft. (12.2 m)					

Note: There <u>MUST</u> be a 25% reduction in total H when using SLP-FLEX Series (6-5/8 inch) vent except when using the simple up and out installation. See Figure 4.8.

INSTALLED HORIZONTALLY

Figure 4.17

Top Vent - Vertical Termination - (continued)

Four 90º Elbows

Note: Use SLP Series components only.

Note: There <u>MUST</u> be a 25% reduction in total H when using SLP-FLEX Series (6-5/8 inch) vent except when using the simple up and out installation. See Figure 4.8.

COSMO42-IFT & COSMO32-IFT									
V_1 MIN.		H_1 MAX.		V_2 MIN.		H_2 MAX.		V_3 MIN.	
2-1/2 ft.	762 mm	4 ft.	1.2 m	4 ft.	1.2 m	4 ft.	1.2 m	3-1/2 ft.	1.0 m
$V_1 + V_2 + V_3 + H_1 + H_2$ Maximum= 40 ft. (12.2 m)									

Figure 4.18

Coaxial to Colinear Venting

The coaxial to colinear adapter (DV-46DVA-GCL) is approved for installations into solid fuel masonry or factory built fireplaces that have been installed in accordance with the National, Provincial, State and local building codes. The DV-46DVA-GCL must be recessed into existing masonry fireplace. See Table 1 and Figure 4.20.

Figure 4.19 Coaxial/Colinear Appliance Adapter (DV-46DVA-GCL)

WARNING! Risk of Fire! *Coaxial to colinear venting configuration may only be used in existing non-combustible chimney. Installation in any other venting application could cause fire.*

Prior to installing the gas appliance:

• Have the chimney and adjacent structure inspected and cleaned by qualified professionals. Hearth & Home Technologies recommends that NFI or CSIA certified professionals, or technicians under the direction of certified professionals, conduct a minimum of a NFPA 211 Level 2 inspection of the chimney.

• Replace component parts of the chimney and fireplace as specified by the professionals.

• Ensure all joints are properly engaged and the chimney is properly secured.

Stainless Steel Flex Requirement - COSMO32-IFT ONLY:

The COSMO32-IFT model requires the use of a 3 ft. stainless steel flex liner (768-380A) to be installed directly to the exhaust collar on the DV-46DVA-GCL connector.

WARNING! Risk of Fire! Risk of Asphyxiation! *Failure to install the stainless steel flex could cause excessive flex vent temperatures.*

• *Aluminum material degradation could cause flex vent system to fail.*

• *Installer MUST install the 3 ft. stainless steel flex on COSMO32-IFT.*

Figure 4.20 Existing Fireplace DV-46DVA-GCL Clearance Requirements

Table 1

CLEARANCE TO COMBUSTIBLES REQUIREMENTS	
DV-46DVA-GCL	3 in. (76 mm)
Exhaust Vent Pipe	5 in (127 mm)

Clearances to Combustibles:

Refer to Section 3 for clearances to the appliance and Section 10 for mantel, mantel legs and wall projection information.

Refer to Section 5 for pipe clearances to combustibles.

Termination Cap

For installation of termination cap see minimum vent heights for various pitched roofs. See Section 4.A.

Flue Damper

Fully lock the solid fuel fireplace's flue damper in the open position, OR completely remove it.

Venting Components

The LINK-DV30B is approved for use with the coaxial/colinear venting application. The LINK-DV30B kit includes:

• Two 30 foot sections of flexible vent pipe (3 inches Ø). One section is used to draw combustion air and the other section is used to expel exhaust gases.

• One vertical termination cap.

CAUTION! DO NOT use any flue restrictor when venting with the DV-46DVA-GCL adapter and LINK-DV30B kit. *This could result in poor flame appearance, sooting, pilot malfunction, or overheating.*

Connecting the DV-46DVA-GCL Adapter to Appliance

Top Vent

- Remove top seal cap and insulation if equipped. See Section 6, "Appliance Preparation." Attach the DV-46DVA-GCL adapter to the appliance starting collar with 3-1/2 in. self-tapping screws. See Figure 4.21.

Connecting the LINK-DV30B to the DV-46DVA-GCL adapter

- Insert the two sections of flexible vent pipe down the existing chimney.

- Attach one section of flexible vent pipe to the exhaust collar on top of the DV-46DVA-GCL adapter with three self-tapping screws.

- Attach one section of flexible vent pipe to the inlet collar on top of the DV-46DVA-GCL adapter with three self-tapping screws.

- To minimize cold air drafts, seal around the flex vents at the damper inside the chimney with non-combustible unfaced fiberglass or rock wool insulation.

The DV-46DVA-GCL adapter must be recessed into existing masonry fireplace. This measurement is taken from the top of the fireplace opening. See Table 1 and Figure 4.20.

WARNING! Risk of Fire, Explosion or Asphyxiation! Do NOT connect this gas appliance to a chimney flue serving a separate solid fuel or gas burning appliance.

- *May impair safe operation of this appliance or other appliances connected to the flue.*
- *Vent this appliance directly outside.*
- *Use separate vent system for this appliance.*

CAUTION! DO NOT use any flue restrictor when venting with the DV-46DVA-GCL adapter and LINK-DV30B kit. This may result in poor flame appearance, sooting, pilot malfunction, or overheating.

*NOTICE: To achieve optimum performance of appliance, minimize or avoid bends in exhaust vent pipe.*

TOP VENT

	V	
Minimum	10 ft.	3.05 m
Maximum	40 ft.	12.2 m

Figure 4.21

5 Vent Clearances and Framing

A. Pipe Clearances to Combustibles

WARNING! Risk of Fire! *Maintain air space clearance to vent.* ***DO NOT*** *pack insulation or other combustibles:*

- *Between ceiling firestops*
- *Between wall shield firestops*
- *Around vent system*

Failure to keep insulation or other material away from vent pipe could cause overheating and fire.

Note: Heat shields MUST overlap by a minimum of 1-1/2 in. (38 mm).
- If wall thickness is less than 4 in. the existing heat shields must be field trimmed. If wall thickness is greater than 7-1/4 in. a DVP-HSM-B will be required.
- **SLP heat shield** - designed to be used on a wall 4-3/8 in. to 7-5/8 in. (111 mm to 194 mm thick).
- If wall thickness is less than 4-3/8 the existing heat shields must be field trimmed. If wall thickness is greater than 7-5/8 in. a DVP-HSM-B will be required.

(SLP Pipe Shown)

3 in. (76 mm) top clearance

Heat Shield

3 in. (76 mm) top clearance *

Heat Shield

1 in. (25 mm) clearance around vertical sections

Wall Shield Firestop

1 in. (25 mm) clearance bottom & sides

WALL

* When using SLP pipe, minimum clearances from the vent pipe to combustible materials at inside wall firestops are:
Top: 2-1/2 in. (64 mm)
Bottom: 1/2 in. (13 mm)
Sides: 1 in. (25 mm)

Figure 5.1 Horizontal Venting Clearances To Combustible Materials

B. Wall Penetration Framing/Firestops

Combustible Wall Penetration

Whenever a combustible wall is penetrated, you must frame a hole for the wall shield firestop(s). The wall shield firestop maintains minimum clearances and prevents cold air infiltration.

- The opening must be framed on all four sides using the same size framing materials as those used in the wall construction.

- SLP pipe - A wall shield firestop must be placed on each side of an interior wall. A minimum 1-1/2 in. (38 mm) overlap of attached heat shields must be maintained.

- See Section 7.F for information for regarding the installation of a horizontal termination cap.

Non-Combustible Wall Penetration

If the hole being penetrated is surrounded by non-combustible materials such as concrete, a hole with diameter one inch greater than the pipe is acceptable.

Whenever a non-combustible wall is penetrated, the wall shield firestop is only required on one side and no heat shield is necessary.

DO NOT PACK WITH INSULATION OR OTHER MATERIAL

10 in.

10 in.

B

A

COSMO32-IFT Shown

	A*	B
COSMO32-IFT	42 in.	41 in.
	1067 mm	1041 mm
COSMO42-IFT	48-1/16	47-1/16
	1221	1195

* Shows center of vent framing hole for top or rear venting. The center of the hole is 1 in. (25 mm) above the center of the horizontal vent pipe.

Figure 5.2 Wall Penetration

C. Ceiling Firestop/Floor Penetration Framing

A ceiling firestop **MUST** be used between floors and attics.

- **SLP pipe only** - Frame opening 9 in. x 9 in. (229 mm x 229 mm) whenever the vent penetrates a ceiling/floor (see Figure 5.3).

- Frame the area with the same sized lumber as used in ceiling/floor joist.

- The ceiling firestop may be installed above or below the ceiling joists when installed with an attic insulation shield. It must be under joists between floors that are not insulated. Refer to Figure 5.4.

- Secure in place with nails or screws.

WARNING! Risk of Fire! DO NOT pack insulation around the vent. Insulation must be kept back from the pipe to prevent overheating.

D. Install Attic Insulation Shield

WARNING! Fire Risk. DO NOT allow loose materials or insulation to touch vent. Hearth & Home Technologies requires the use of an attic shield.

The International Fuel Gas Code requires an attic shield constructed of 26 gauge minimum steel that extends at least 2 in. (51 mm) above insulation.

- Attic insulation shields must meet specified clearances to combustible materials and be secured in place.

- An attic insulation shield kit is available from Hearth & Home Technologies. Contact your dealer to order. Install attic insulation shield according to instructions included with kit.

ATTIC ABOVE

PIPE	A
SLP	9 in. (229 mm)

Figure 5.3 Installing Ceiling Firestop

INSTALL ATTIC INSULATION SHIELDS
BEFORE OR AFTER INSTALLATION OF VENT SYSTEM

CEILING FIRESTOP
INSTALLED BELOW CEILING

CEILING FIRESTOP
INSTALLED ABOVE CEILING

Figure 5.4 Installing the Attic Shield

6 Appliance Preparation

A. Vent Collar Preparation

CAUTION! Risk of Cuts, Abrasions or Flying Debris.
Wear protective gloves and safety glasses during installation. Sheet metal edges are sharp.

NOTICE: Once appliance is set up for top or rear venting, it CANNOT be changed at a later time.

WARNING! Risk of Fire! *Do not remove heat shield. Elevated header temperatures may cause a fire.*

COSMO42-IFT
1. Remove two screws and discard. See Figure 6.1.
2. Fold up top heat shield to 90 degrees as shown in Figure 6.2.

Figure 6.1 COSMO42-IFT - Shipping Position

Figure 6.2 COSMO42-IFT - Top Heat Shield in Position

COSMO32-IFT

1. Remove two screws and remove shipping support. See Figure 6.3.

2. Remove and discard shipping support, seal cap, and screws. See Figure 6.4.

Figure 6.3 COSMO32-IFT - Shipping Support in Shipping Position

Figure 6.4 COSMO32-IFT - Shipping Support and Seal Cap Removed

B. Installing Optional Heat Management Systems

NOTICE: *Additional clearances are required for heat management systems installations. Provisions must be made in advance to ensure fit within the framing.*

• Locate the heat management ports on the left and right sides of the appliance. Either one or two Heat-Zone® -Gas Kits may be installed. See Figure 6.2. Remove the knockouts from the appliance with a tin snips.

• Center the duct collar around the exposed hole and attach it to the appliance with 3 screws. Note: Do this BEFORE final positioning of the appliance.

• Determine the location for the air register/fan housing assembly.

Reference the Heat-Zone®-Gas Kit, Smart-Wall™ TV Kit, Heat-Duct Kit or Heat-Out-Gas Kit instructions for the remaining installation steps.

Smart-Wall™ TV Kit
When a Smart-Wall™ TV Kit is installed, only one Heat-Zone® -Gas kit or one Heat-Out-Gas kit may be installed. The Smart-Wall™ TV Kit can not be used with a power vent option or optional fan.

C. Securing and Leveling the Appliance

WARNING! Risk of Fire! *Prevent contact with:*

• *Sagging or loose insulation*
• *Insulation backing or plastic*
• *Framing and other combustible materials*

Block openings into the chase to prevent entry of blown-in insulation. Make sure insulation and other materials are secured.

DO NOT *notch the framing around the appliance standoffs.*

Failure to maintain air space clearance could cause overheating and fire.

The COSMO42-IFT and COSMO32-IFT models ship with factory-installed non-combustible board. This board must be used. Do NOT remove. See Figure 6.5.

The diagram shows how to properly position and secure the appliance. See Figure 6.5. Nailing tabs are provided to secure the appliance to the framing members.

• Bend out nailing tabs on each side.

• Place the appliance into position.

• Keep nailing tabs flush with the framing.

• Level the appliance from side to side and front to back.

• Shim the appliance as necessary. It is acceptable to use wood shims underneath the appliance.

• Secure the appliance to the framing by using nails or screws through the nailing tabs.

• Optional: Secure the appliance to the floor by inserting two screws through the pilot holes at the bottom of the appliance.


FACTORY-INSTALLED NON-COMBUSTIBLE BOARD DO NOT REMOVE

NAILING TABS BOTH SIDES

Figure 6.5   Proper Positioning, Leveling And Securing Of Appliance

D. Non-Combustible Material Installation

WARNING! Risk of Fire! *DO NOT remove factory-installed non-combustible material.*

This model ships with the required top, left and right non-combustible board. The top non-combustible board has been pre-installed at the factory with three screws. The left and right side non-combustible boards are shipped in the cardboard splatter guard in front of the appliance. See Figure 6.6.

1. Remove the left and right non-combustible components from the shipping position and set aside.

2. Remove the lower cover panel by removing two screws located on the lower left and right sides of the appliance opening. Retain screws. Lift the lower cover panel "up" and "out" to remove.

3. Locate the manual bag assembly and remove the small package containing the 1-1/2 inch Phillips screws.

Note: Care should be taken when installing screws into the non-combustible board. DO NOT overtighten screws. Screws should be set "flush" to the surface of the non-combustible board.

4. Further secure the top non-combustible board by installing screws into the pilot holes located in the upper left and right corners of the top non-combustible board as shown in Figure 6.7.

5. Install the left and right non-combustible components with four of the provided Phillips screws. See Figure 6.7.

6. Install drywall screws (not provided) around the perimeter of the installed non-combustible components to secure it to the framing material. Refer to Section 10 for more information.

Figure 6.6 Shipping Position - Non-Combustible Sides

Figure 6.7 Installation of the Side Non-Combustible Components

7 Venting and Chimneys

A. Assemble Vent Sections

(SLP Only)

To attach the first vent component to the starting collars of the appliance:

- Lock the vent components into place by sliding the pipe section onto the collar.

- Align the seam of the pipe and seam of collar to allow engagement. Rotate the vent component to lock into place. Use this procedure for all vent components. See Figure 7.2.

- Slide the gasket over the first vent section and place it flush to the appliance. This will prevent cold air infiltration. Caulk with a minimum of 300 ºF continuous exposure rating may be used to hold the part in place.

- Continue adding vent components, locking each succeeding component into place.

- Ensure that each succeeding vent component is securely fitted and locked into the preceding component.

It is acceptable to use screws no longer than 1/2 in. (13 mm) to hold outer pipe sections together. If predrilling holes, **DO NOT** penetrate inner pipe.

Required Commercial, Multi-family (Multi-level exceeding two stories), or High-Rise Applications

All outer pipe joints must be sealed with high temperature silicone (300 ºF minimum continuous exposure rating), including the slip section that connects directly to the horizontal termination cap.

- Apply a bead of silicone sealant (300 ºF minimum continuous exposure rating) to the outside of connecting joint after joining sections. See Figure 7.1. **OR**

  Apply aluminum foil tape (300 ºF minimum continuous exposure rating) to the outside of connecting joint after joining sections. On horizontal pipe runs, it is recommended that the tape seam is positioned on the bottom side of the vent pipe.

- Only outer pipes need to be sealed. All unit collar, pipe, slip section, elbow and cap outer flues shall be sealed in this manner, unless otherwise stated.

WARNING! Risk of Fire or Explosion! DO NOT break silicone seals on slip sections. Use care when removing termination cap from slip pipe. If slip section seals are broken during removal of the termination cap, vent could leak.


Figure 7.1 High Temperature Silicone Sealant

Note: Align seams to engage pipe, then rotate counterclockwise to lock

Figure 7.2 Adding Venting Components

B. Assemble Slip Sections

• Slide the inner flue of the slip section into the inner flue of the pipe section and the outer flue of the slip section over the outer flue of the pipe section. See Figure 7.3.

• Slide together to the desired length.

Pilot hole

Figure 7.3 Slip Section Pilot Holes

• Maintain a 1-1/2 in. (38 mm) overlap between the slip section and the pipe section.

• Secure the pipe and slip section with two screws no longer than 1/2 in. (13 mm), using the pilot holes in the slip section. See Figure 7.4.

Figure 7.4 Screws into Slip Section

• Continue adding pipe as necessary following instructions in "Assembling Pipe Sections."

NOTICE: *If slip section is too long, the inner and outer flues of the slip section can be cut to the desired length.*

C. Secure the Vent Sections

• Vertical runs originating off the top of the appliance, with no offsets, must be supported every 8 ft. (2.44 m) after the maximum allowed 25 ft. (7.62 m) of unsupported rise.

• Vertical runs originating off the rear of the appliance, or after any elbow, must be supported every 8 ft. (2.44 m).

• Horizontal runs must be supported every 5 feet (1.52 m).

• Vent supports or plumbers strap (spaced 120° apart) may be used to support vent sections. See Figures 7.5 and 7.6.

• Wall shield firestops may be used to provide horizontal support to vent sections.

• SLP ceiling firestops have tabs that may be used to provide vertical support.

WARNING! Risk of Fire, Explosion or Asphyxiation! *Improper support could allow vent to sag and separate. Use vent run supports and connect vent sections per installation instructions.* ***DO NOT*** *allow vent to sag below connection point to appliance.*

Figure 7.5 Securing Vertical Pipe Sections

Figure 7.6 Securing Horizontal Pipe Sections

D. Disassemble Vent Sections

• Rotate either section (see Figure 7.7) so the seams on both pipe sections are aligned as shown in Figure 7.8.

• Pull carefully to separate the pieces of pipe.

**Figure 7.7 Rotate Seams for Disassembly**

Figure 7.8 Align and Disassemble Vent Sections

E. Vertical Termination Requirements

Install Metal Roof Flashing

- See minimum vent heights for various pitched roofs (Figure 7.9) to determine the length of pipe to extend through the roof.

- Slide the roof flashing over the pipe sections extending through the roof as shown in Figure 7.10.


Figure 7.9 Minimum Height From Roof to Lowest Discharge Opening

Roof Pitch	H (Min.) Ft.
Flat to 6/12	1.0*
Over 6/12 to 7/12	1.25*
Over 7/12 to 8/12	1.5*
Over 8/12 to 9/12	2.0*
Over 9/12 to 10/12	2.5*
Over 10/12 to 11/12	3.25
Over 11/12 to 12/12	4.0
Over 12/12 to 14/12	5.0
Over 14/12 to 16/12	6.0
Over 16/12 to 18/12	7.0
Over 18/12 to 20/12	7.5
Over 20/12 to 21/12	8.0

* H minimum may vary depending on regional snowfall. Refer to local codes.

NOTICE: Failure to properly caulk the roof flashing and pipe seams could permit entry of water.

- Caulk the gap between the roof flashing and the outside diameter of the pipe.

- Caulk the perimeter of the flashing where it contacts the roof surface. See Figure 7.10.

- Caulk the overlap seam of any exposed pipe sections that are located above the roof line.

Figure 7.10

Assemble and Install Storm Collar

CAUTION! Risk of Cuts, Abrasions or Flying Debris. Wear protective gloves and safety glasses during installation. Sheet metal edges are sharp.

- Slide the storm collar onto the exposed pipe section and align brackets.
- Insert a bolt (provided) through the brackets and install nut. Do not completely tighten.

Figure 7.11 Insert Bolt into Brackets

- Slide the assembled storm collar down the pipe section until it rests on the roof flashing. See Figure 7.11.

- Tighten nut and make sure the collar is tight against the pipe section.

- Caulk around the top of the storm collar. See Figure 7.12.

Install Vertical Termination Cap

• Attach the vertical termination cap by sliding the inner collar of the cap into the inner flue of the pipe section while placing the outer collar of the cap over the outer flue of the pipe section.

• Secure the cap by driving three self-tapping screws (supplied) through the pilot holes in the outer collar of the cap into the outer flue of the pipe. See Figure 7.12.


Figure 7.12

F. Horizontal Termination Requirements

Heat Shield Requirements for Horizontal Termination

WARNING! Risk of Fire! *To prevent overheating and fire, heat shields must extend through the entire wall thickness.*

   • ***DO NOT*** *remove the heat shields attached to the wall shield firestop and the horizontal termination cap (shown in Figure 7.13).*

   • *Heat shields must overlap 1-1/2 in. (38 mm) minimum.*

There are two sections of the heat shield. One section is factory-attached to the wall shield firestop. The other section is factory-attached to the cap. See Figure 7.13.

If the wall thickness does not allow the required 1-1/2 in. (38 mm) heat shield overlap when installed, an extended heat shield must be used.

• If the wall thickness is less than 4 in./102 mm (DVP) or 4-3/8 in./ 111 mm (SLP), the heat shields on the cap and wall shield firestop must be trimmed. A minimum 1-1/2 in. (38 mm) overlap MUST be maintained.

• Use an extended heat shield if the finished wall thickness is greater than 7-1/4 in. (184 mm).

• The extended heat shield may need to be cut to length maintaining sufficient length for a 1-1/2 in. (38 mm) overlap between heat shields.

• Attach the extended heat shield to either of the existing heat shields using the screws supplied with the extended heat shield. Refer to vent components diagrams in the back of this manual.

• Rest the small leg on the extended heat shield on top of the pipe section to properly space it from the pipe section.

Important Notice: Heat shields may <u>not</u> be field constructed.

Install Horizontal Termination Cap

WARNING! Risk of Fire! *The telescoping flue section of the termination cap MUST be used when connecting vent.*

- *1-1/2 (38 mm) minimum overlap of flue telescoping section is required.*

Failure to maintain overlap could cause overheating and fire.

- Vent termination must not be recessed in the wall. Siding may be brought to the edge of the cap base.

- Flash and seal as appropriate for siding material at outside edges of cap.

- When installing a horizontal termination cap, follow the cap location guidelines as prescribed by current **ANSI Z223.1** and **CAN/CGA-B149** installation codes and refer to Section 4 of this manual.

CAUTION! Risk of Burns! *Local codes may require installation of a cap shield to prevent anything or anyone from touching the hot cap.*

Note: When using termination caps with factory-supplied heat shield attached, no additional wall shield firestop is required on the exterior side of a combustible wall.

Figure 7.13 Venting Through the Wall

8 | Electrical Information

A. General Information

***WARNING! Risk of Shock or Explosion! DO NOT** wire 110-120 VAC to the valve or to the appliance wall switch. Incorrect wiring will damage controls.*

NOTICE:** This appliance must be electrically wired and grounded in accordance with local codes or, in the absence of local codes, with **National Electric Code ANSI/NFPA 70-latest edition** or the **Canadian Electric Code CSA C22.1.

- Wire the appliance junction box to unswitched 110-120 VAC. This is required for proper operation of the appliance.

- A 110-120 VAC circuit for this product must be protected with ground-fault circuit-interrupter protection, in compliance with the applicable electrical codes, when it is installed in locations such as in bathrooms or near sinks.

- Low voltage and 110-120 VAC voltage cannot be shared within the same wall box.

- In some instances, the spark ignition of the fireplace may cause intermittent, non-damaging, interference during the lighting sequence with a TV plugged into the same circuit. It is recommended that the fireplace and TV use different circuits to mitigate the interference potential. If interference is occurring on the same circuit, the use of surge protectors may help alleviate the interference.

Valve/Control Access

The valve/control cavity is accessible by removing two screws located in the lower right and left corners of the fireplace opening. See Figure 8.1.

Once finishing material has been installed, access to the valve/control cavity is limited to access through the firebox, see Section 9.B.


Figure 8.1 Remove Lower Access Panel

Junction Box Installation

If the box is being wired from the INSIDE of the appliance:

COSMO42-IFT: The junction box is secured to a bracket. Remove one screw. See Figure 8.2.

COSMO32-IFT: The junction box is secured to the fireplace outer wrap. Remove one screw. See Figure 8.3.

- Pull the electrical wires from outside the appliance through the opening into the valve compartment and secure wires with a Romex connector. See Figure 8.4.

- Make all necessary wire connections to the junction box/receptacle and reattach the junction box/receptacle to the outer shell (COSMO32-IFT) or bracket (COSMO42-IFT).


**Figure 8.2 Junction Box Detail - COSMO42-IFT**

**Figure 8.3 Junction Box Detail - COSMO32-IFT**

Figure 8.4. Junction Box Wiring (Generic Model Shown)

Accessories Requirements

• This appliance may be used with a wall switch, wall mounted thermostat and/or a remote control.

Wiring for optional Hearth & Home Technologies approved accessories should be done now to avoid reconstruction. Follow instructions that come with those accessories.

Electrical Service and Repair

WARNING! Risk of Shock! Label all wires prior to disconnection when servicing controls. Wiring errors could cause improper and dangerous operation. Verify proper operation after servicing.

WARNING! Risk of Shock! Replace damaged wire with type 105º C rated wire. Wire must have high temperature insulation.

B. Wiring Requirements

Intellifire™ Touch Ignition System Wiring

• Wire the appliance junction box to 110-120 VAC for proper operation of the appliance.

WARNING! Risk of Shock or Explosion! DO NOT wire IPI controlled appliance junction box to a switched circuit. Incorrect wiring will override IPI safety lockout.

• Refer to Figures 8.5, 8.6, and 8.7 wiring diagrams.

• This appliance is equipped with an IntelliFire™ Touch control valve which operates on a 6 volt/1.5 AMP system.

• Plug the 6 volt transformer plug into the appliance junction box to supply power to the unit OR install 4 AA cell batteries (not included) into the battery pack before use.

NOTICE: Batteries should only be used as a power source in the event of an emergency power outage. Batteries should not be used as a primary long-term power source. Battery polarity must be correct when installing batteries. When using batteries as a power source, the 6-volt transformer must be unplugged from the receptacle.

Do not store batteries in the battery pack when the appliance is powered by the 6 volt transformer connected to permanent electrical service.

JUNCTION BOX
110-120 VAC

INTERMITTENT
PILOT IGNITER (NG)
2106-169

6 VAC
TRANSFORMER
2326-131

RESET SWITCH
2206-298

WHITE   ORANGE

RESET SWITCH WIRE
2550-135

I S

IFT CONTROL MODULE
2326-130

**Note: Battery Pack located in control cavity
of appliance as shown in DETAIL A below.**

WIRE HARNESS
2326-132

RED

RED

BLACK

6V BATTERY PACK
2326-134

VALVE (NG)
2166-302

ORANGE

GREEN

RED

BLK

JUMPER
2187-198

ORANGE

GROUND TO
FIREPLACE
CHASSIS

DETAIL A

GREEN

BRN

RED

WHITE

WIRE ASSEMBLY
2118-170

BATTERY PACK

Figure 8.5 Intellifire™ Touch Wiring Diagram - Standard

6 VAC TRANSFORMER 2326-131

JUNCTION BOX 110-120 VAC

AC MODULE CABLE 2326-152

HOT   **NEUTRAL**

INTERMITTENT PILOT IGNITER (NG) 2106-169

OPTIONS

RESET SWITCH 2206-298

RESET SWITCH WIRE 2550-135

FAN GFK-160A

IFT CONTROL MODULE 2326-130

IFT AUX 2326-150

FAN OUTLET

RF MODULE 2326-120

IFT-RC400 REMOTE CONTROL

IFT-AUX 2326-150

RF MODULE 2326-120

AC MODULE CABLE 2326-152

LED CONTROL

NOT USED

LED's

ORANGE (PILOT)   **GREEN (MAIN)**

RED

WIRE HARNESS

RF MODULE 2326-120

APPLIANCE ON/OFF CONTROL   **BRN**   **BLK**

JUMPER WIRE

RED
BLK

6V DC BATTERY PACK 2326-134

IFT-RC150 WIRELESS WALL SWITCH

LED-LINEAR
Components shown in diagram.

Figure 8.6 Intellifire™ Touch Wiring Diagram with Remote, Fan and LED Options

JUNCTION BOX
110-120 VAC

AC MODULE CABLE
2326-152

6 VAC
TRANSFORMER
2326-131

IFT-RC400 REMOTE CONTROL
2326-110

INTERMITTENT
PILOT IGNITOR
(2106-169)

RESET SWITCH
2206-298

RESET SWITCH WIRE
2550-135

WHITE   ORANGE

S

I

OPTIONAL FAN
GFK-160A

IFT CONTROL MODULE
2326-130

IFT AUX
2326-150

RF MODULE
2326-120

WIRE HARNESS
2326-132

VALVE (NG)
2166-302

ORANGE

GREEN

BRN

BLK

RED

JUMPER
2155-033

WIRE HARNESS
PVI-WH10
PVI-WH20
PVI-WH40
PVI-WH60
PVI-WH80
PVI-WH100

ORANGE

GROUND TO
FIREPLACE
CHASSIS

PVI-SLP-B OR PVLP-SLP

GREEN

PVLP-SLP

PVI-SLP-B

Figure 8.7 Intellifire™ Touch Wiring Diagram with Power Vent Diagram

9 Gas Information

A. Fuel Conversion

• Make sure the appliance is compatible with available gas types.

• Conversions must be made by a qualified service technician using Hearth & Home Technologies specified and approved parts.

B. Gas Pressure

• Optimum appliance performance requires proper input pressures.

• Gas line sizing requirements will be determined in ANSI Z223.1 National Fuel Gas Code in the USA and CAN/CGA B149 in Canada.

• Pressure requirements are:

Gas Pressure	Natural Gas	Propane
Minimum inlet pressure	5.0 in. w.c.	11.0 in. w.c.
Maximum inlet pressure	10.0 in. w.c.	13.0 in. w.c.
Manifold pressure	3.5 in. w.c.	10.0 in. w.c.

WARNING! Risk of Fire or Explosion! High pressure will damage valve. Low pressure could cause explosion.

• Verify inlet pressures. Verify minimum pressures when other household gas appliances are operating.

• Install regulator upstream of valve if line pressure is greater than 1/2 psig.

⚠ WARNING

Fire Risk.

Explosion Hazard.

High pressure will damage valve.

• Disconnect gas supply piping BEFORE pressure testing gas line at test pressures above 1/2 psig.

• Close the manual shutoff valve BEFORE pressure testing gas line at test pressures equal to or less than 1/2 psig.

Note: Have the gas supply line installed in accordance with local codes, if any. If not, follow ANSI Z223.1. Installation should be done by a qualified installer approved and/or licensed as required by the locality. (In the Commonwealth of Massachusetts installation must be performed by a licensed plumber or gas fitter).

Note: A listed (and Commonwealth of Massachusetts approved) 1/2 in. (13 mm) T-handle manual shut-off valve and flexible gas connector are connected to the 1/2 in. (13 mm) control valve inlet.

• **If substituting for these components, please consult local codes for compliance.**

Access Through the Control Cavity
(For Service/Conversion)

The lower access cover panel is removable if finishing material has not been previously installed. See Section 8.A for removal instructions.

Access Through the Valve Assembly
(For Service/Conversion)

1. Locate and remove the two screws that secure the basepan to the appliance. See Figure 9.1. Remove basepan. Retain screws.


REMOVE 2 SCREWS

Figure 9.1 Basepan Removal - COSMO42-IFT Shown

2. Remove the two screws that secure the pilot shield to the burner bracket and remove the two screws that secure the pilot assembly to the burner bracket. Remove the one screw that secures the burner bracket to the valve plate. See Figure 9.2. Gently push the pilot assembly backwards to allow for the burner to be removed.

3. Remove the screw that secures the burner bracket to the valve plate. See Figure 9.2.

4. Slide burner assembly to the left to disengage the burner tube from the orifice. Remove the burner from the appliance.

5. Remove the nine screws around the perimeter of the valve plate that secure valve plate to the appliance. See Figure 9.3.

6. Lift up on the plate assembly. Ensure the gas ball valve is turned off. Disconnect the ball valve assembly from the gas valve by loosening the compression fitting located on the left side of the gas valve.

7. Prior to removing valve assembly for service, disconnect the pilot wires from the ignition module.

8. Upon completion of service, reverse steps 1-7. If the valve plate gasket is damaged, replace the gasket prior to reinstallation of valve plate assembly.

REMOVE PILOT SCREWS

REMOVE BURNER SCREW

Figure 9.2 Burner Removal

REMOVE 9 SCREWS

Figure 9.3 Remove Valve Plate

Note: Install the gas supply line in accordance with local codes, if any. If not, follow ANSI 223.1. Installation should be done by a qualified installer approved and/or licensed as required by the locality. (In the Commonwealth of Massachusetts installation must be performed by a licensed plumber or gas fitter).

Note: A listed (and Commonwealth of Massachusetts approved) 1/2 in. (13 mm) T-handle manual shut-off valve and flexible gas connector are connected to the 1/2 in. (13 mm) control valve inlet.

• **If substituting for these components, please consult local codes for compliance.**

Valve Pressure Taps

The pressure taps are accessible by removing the lower panel prior to finishing material installation. There is limited access to the pressure taps after finishing material installation. Remove glass assembly and utilize an appropriate sized screwdriver.

C. Gas Connection

- Refer to Reference Section 3 for location of gas line access in appliance.

- Gas line may be run through knockout(s) provided.

- The gap between supply piping and gas access hole may be caulked with caulk with a minimum of 300 °F continuous exposure rating or stuffed with non-combustible, unfaced insulation to prevent cold air infiltration.

- Ensure that gas line does not come in contact with outer wrap of the appliance. Follow local codes.

- Pipe incoming gas line into valve compartment.

Note: It is important to plumb the incoming gas line to the location specified inside the appliance. This specific location allows for future serviceability of the appliance. See Figure 9.4

- Connect incoming gas line to the 1/2 in. (13 mm) connection on manual shutoff valve.

WARNING! Risk of Fire or Explosion! Support control when attaching pipe to prevent bending gas line.

- A small amount of air will be in the gas supply lines.

WARNING! Risk of Fire or Explosion! Gas build-up during line purge could ignite.

- *Purge should be performed by qualified service technician.*

- *Ensure adequate ventilation.*

- *Ensure there are no ignition sources such as sparks or open flames.*

Light the appliance. It will take a short time for air to purge from lines. When purging is complete the appliance will light and operate normally.

*WARNING! Risk of Fire, Explosion or Asphyxiation! Check all fittings and connections with a non-corrosive commercially available leak-check solution. **DO NOT** use open flame. Fittings and connections could have loosened during shipping and handling.*

*WARNING! Risk of Fire! DO NOT change valve settings. This valve has been preset at the factory.*

Figure 9.4 Incoming Gas Line Location

D. High Altitude Installations

NOTICE: *If the heating value of the gas has been reduced, these rules do not apply. Check with your local gas utility or authorities having jurisdiction.*

When installing above 2000 feet elevation:

- In the USA: Reduce input rate 4% for each 1000 feet above 2000 feet.

- In CANADA: Input ratings are certified without a reduction of input rate for elevations up to 4500 feet (1370 m)above sea level. Please consult provincial and/or local authorities having jurisdiction for installations at elevations above 4500 feet (1370 m).

Check with your local gas utility to determine proper orifice size.

E. Air Shutter Setting

Air shutter settings should be adjusted by a qualified service technician at the time of installation. The air shutter is set at the factory for minimum vertical vent run. Adjust air shutter for longer vertical runs. See Figure 9.5.

- Loosen the 1/4 inch screw.

- Twist the air shutter to adjust.

- Air shutter may be opened for longer horizontal vent runs.

- Tighten the 1/4 inch screw.

NOTICE: *If the flames appear to be orange or sooting occurs, open the air shutter to prevent residue buildup on the glass.*


Figure 9.5 Air Shutter Location

Air Shutter Settings

	NG	Propane
COSMO32-IFT	1/16 in.	1/8 in.
COSMO42-IFT	1/16 in.	3/16 in.

10 Finishing

A. Facing Materials

WARNING! Risk of Fire! Comply with all minimum clearances to combustibles as specified. Framing closer than the minimums listed must be constructed entirely of noncombustible materials (i.e., steel studs, concrete board, etc.)

The appliance is designed to accept 1/2 in. wall sheathing materials such as drywall, plywood, wood composites, or non-combustible materials. The type of material used depends whether the installation is an Inside or Overlap Fit Method. Refer to Section 10.D regarding installation details associated with the Inside and Overlap Fit methods.

The factory-supplied non-combustible board must be used in all installations. It must be directly attached to structural framing adjacent to the appliance. Screw fasteners should be installed in the pilot holes provided in the outer perimeter of the non-combustible board. See Figure 10.1 and Figure 10.2.

The factory-supplied board is designed such that its edges will be at the approximate center of the adjacent framing, assuming it is 1-1/2 in. nominal thickness. This will allow the wallboard joints to occur on the center of the framing where the panels can be fastened properly. If the framing thickness is less than 1-1/2 in. nominal, such as with formed steel systems, then it may be necessary to adjust the adjacent framing dimensions so that the non-combustible board and wallboard joints are centered on the framing.

Finishing Instructions

It is important to follow the framing and finishing instructions to ensure proper placement of fireplace into the surrounding framing/finishing materials.

Wall sheathing materials 1/2 in. thick are specified in this installation manual to properly align with the factory-installed non-combustible material.

WARNING! Risk of Fire! DO NOT remove the factory-installed non-combustible board or cover it with combustible material, such as:

- *Drywall (gypsum board)*
- *Plywood*
- *Materials that do not meet the ASTM E 136 Non-combustibility standard (below).*

Removal of factory-installed, non-combustible board and/or use of materials not meeting the ASTM E 136 standard may cause fire.

- Facing and/or finishing materials must not interfere with air flow through decorative fronts.
- Facing and/or finishing materials must never overhang into the glass opening.

- Observe all clearances when applying combustible materials.

WARNING! Risk of Fire! DO NOT apply combustible materials beyond the minimum clearances. Comply with all minimum clearances to combustibles as specified in this manual. Overlapping materials could ignite and will interfere with proper operation of decorative fronts.

WARNING! Risk of Fire! DO NOT install drywall or other combustible materials over the factory-installed non-combustible board. Overlapping materials could ignite.

Decorative facing material thickness is measured from the face of the factory-installed non-combustible board. See Section 10.D for Overlap Fit and Inside Fit requirements.

Non-Combustible Materials Specification

Material which will not ignite and burn. Such materials are those consisting entirely of steel, iron, brick, tile, concrete, slate, glass or plasters, or any combination thereof.

Materials that are reported as passing **ASTM E 136, Standard Test Method for Behavior of Materials in a Vertical Tube Furnace at 750 ºC.**

B. Non-Combustible Board and Drywall Installation

Introduction

If the desired finished fireplace installation does not utilize non-combustible finishing materials (such as tile, marble, stone, etc.), special attention must be paid to the installation of drywall/gypsum wallboard to minimize potential development of cracking and paint discoloration. Hearth and Home Technologies has tested the following methods and materials and therefore recommends the following steps for the best drywall performance.

Attaching Non-Combustible Board to Framing

1. To ensure the lower cover panel has been correctly installed, verify that two screws (total) have been installed in the lower left and right sides of the fireplace opening. See Figure 8.1. These screws, when installed, will ensure the lower panel is correctly installed. If the lower cover panel is not correctly installed, the decorative front may not fit into the fireplace opening correctly. Refer to section 6.D for more information regarding the included non-combustible board.

2. The appliance ships with the required non-combustible board. The large top piece of non-combustible board is pre-installed at the factory. The narrow left and right non-combustible pieces are shipped within the appliance. Install the non-combustible side pieces with the screws provided in the manual bag assembly. There are pilot holes located on the left and right side columns. Care should be taken not to tighten these screws into the non-combustible board excessively. Set screws flush to the face of the non-combustible board. See Figure 10.2 and Section 6.D.

3. The outer perimeter of the factory-installed non-combustible board has pre-drilled pilot holes. See Figure 10.1. Secure the non-combustible board to adjacent framing with drywall screws that are a minimum of 1-1/4 inch in length. Care should be taken not to tighten these screws into the non-combustible board excessively. Set screws flush to the face of the non-combustible board. See Figure 10.2 and Section 6.D.

4. When installing drywall around the appliance, install a rectangular hole for the fireplace/non-combustible board in a single sheet of drywall. This will minimize the joints that require finishing adjacent to the fireplace opening. Ensure that the 1/8 inch gap is maintained between the factory installed non-combustible board and the surrounding drywall. See Figure 10.1. Secure the drywall to the framing with screws a minimum of one inch in length every six inches across the top of the fireplace and every ten inches on the sides of the fireplace.

5. To ensure good adhesion of drywall compounds and tape, thoroughly clean the non-combustible board and surrounding drywall to remove dust. The non-combustible board may be primed with a high-quality PVA primer.


Figure 10.1 Install Non-Combustible Board

Filling and Finishing Seams

1. **Step 1:** Fill all gaps and joints between the non-combustible board pieces and the drywall with a general purpose chemically setting joint compound such as Durabond® 45 Joint Compound manufactured by USG (Sheetrock® brand), recommended by Hearth & Home Technologies. Use a drywall knife to firmly press the joint compound into all gaps. See Figure 10.1. Allow these joints to dry.

2. **Step 2:** All joints are to be taped with fiberglass mesh tape 1 7/8" minimum width, and embedded with Setting-Type joint compound, such as with Durabond® Joint Compound manufactured by USG (Sheetrock® brand), or equivalent. Allow these joints to dry.

3. **Step 3:** Depending on the technique used in steps 1 and 2, two to three finishing coats are required to provide a smooth and durable finish. Hearth and Home Technologies recommends a lightweight or all-purpose compound. Allow each coat to properly cure. Allow the finishing coat(s) to cure for 24 hours before operating appliance.

Painting

If desired finishing includes a painted wall, a high-quality 100% acrylic latex paint with a high-quality latex primer base coat are recommended around the appliance to limit discoloration. Oil-based or standard acrylic paints may be more prone to discoloration due to heat exposure.

### Drywall Joint-Crack Prevention and Repair

Drywall joints around the fireplace will be affected by exposure to elevated temperatures, along with other environmental, structural factors due to new construction, and methods used to install and finish the drywall. If a crack does emerge adjacent to the fireplace, it can be permanently repaired by filling it with a paintable latex caulk, followed by repainting.

Some movement of the screws used to secure the non-combustible board to the appliance/surround framing is expected. If a blemish begins to show over a screw head, sand the surface to remove the blemish and repaint.

WARNING! Risk of Fire! Maintain specified air space clearances to combustibles. Inadequate air space could cause overheating and fire.

WARNING! Risk of Fire! **Maintain specified air space clearances to combustibles.** *Failure to comply with these instructions may cause a fire or cause the appliance to overheat.*

Note: If the desired look is painted drywall, it is recommended that no additional screws are installed into the factory-provided non-combustible board. Only install the screws provided into the pilot holes located in the factory-provided non-combustible board.

PILOT HOLES (11 LOCATIONS) TO ATTACH NON-COMBUSTIBLE BOARD TO FRAMING

FACTORY-INSTALLED NON-COMBUSTIBLE BOARD

LOWER COVER PANEL

= **1 INCH. MAX. SELF-TAPPING SCREWS ALLOWED**

= **NO SCREWS ALLOWED**

= **5 INCH - 7 INCH SELF-TAPPING SCREWS ALLOWED**

Note: It is acceptable to use a silicone sealant with a minimum of 300 ºF continuous exposure rating to adhere drywall to lower cover panel.

Figure 10.2 Finishing Details - COSMO42-IFT and COSMO32-IFT

CAUTION! Risk of Glass Damage and Cuts! *DO NOT drill or install any type of screw or fastener into the lower cover panel. Sharp screw or fastener tips may penetrate and break the glass or cause cuts.*

The final fireplace installation can be accomplished by either the Overlap Fit or Inside Fit method. Reference Section 10.D regarding installation details associated with the Inside Fit and Overlap Fit methods.

It is acceptable to pre-drill holes and use self-tapping screws in the installed non-combustible board to attach non-combustible backer board for tile, marble, etc. Refer to Figure 10.2 for acceptable screw or metal lath location and screw length requirements.

Do not drill or install screws which may penetrate the lower cover panel as this will restrict required access to the glass, battery-backup, and control module. See Figure 10.2.

C. Mantel and Wall Projections

WARNING! Risk of Fire! Comply with all minimum clearances as specified. Framing closer than the minimums listed must be constructed entirely of non-combustible materials (i.e., steel studs, concrete board, etc.).

Note: Measurement is taken from top of the opening, NOT the top of the fireplace.

Non-combustible Mantels

1/2 IN. THICK WALL SHEATHING →

12 IN. MAX.

NON-COMBUSTIBLE MANTEL

NON-COMBUSTIBLE MANTEL

14 IN. MIN. BOTTOM OF MANTEL TO TOP OF APPLIANCE OPENING

6 IN. MAX.

APPLIANCE OPENING

Figure 10.4   Clearances To Non-Combustible Mantels Or Other Non-Combustibles Above Appliance

Combustible Mantels

12 IN. MAX.

COMBUSTIBLE MANTEL

1/2 IN. THICK WALL SHEATHING →

14 IN. MIN. BOTTOM OF MANTEL TO TOP OF APPLIANCE OPENING

APPLIANCE OPENING

Figure 10.3   Clearances To Combustibles Mantels Or Other Combustibles Above Appliance

Mantel Legs Or Wall Projections Extending Past The Face Of The Fireplace (Combustible or Non-Combustible)

Note: Clearance from opening to perpendicular wall.

6 IN. MIN.

APPLIANCE OPENING

WALL 3 FT. MAX.

Figure 10.5 Combustible or Non-Combustible Mantel Leg or Wall Projections (Acceptable on both sides of opening)

Note: Clearance from opening to perpendicular wall.

7 IN. MIN.

APPLIANCE OPENING

WALL UNLIMITED

Figure 10.6 Combustible or Non-Combustible Mantel Leg or Wall Projections - Unlimited Wall Length (Acceptable on both sides of opening)

D. Decorative Front Finishing

WARNING! Risk of Fire! *A decorative front is required for this model. DO NOT operate this appliance without a decorative front in place.*

Only decorative fronts certified for use with this appliance model may be used. Contact your dealer for a list of decorative fronts that may be used.

Overlap Fit - CFT and Martini Decorative Fronts (0 Inches to 1 Inch Thick Finishing Material)

Both the CFT and Martini decorative fronts are designed to overlap finish materials 0 inches to 1 inch thick. See Figure 10.7 and Figure 10.8.

NOTICE: *This one inch maximum not only includes the decorative finish materials (marble, tile, slate, etc) but also the mortar or adhesive used to attach the decorative finish material.*

The non-combustible finish material can be installed up to the fireplace opening.

Finishing materials 1 inch maximum thick.
Stop finishing material flush with opening.

Figure 10.7   Overlap Fit Decorative Front (CFT and Martini Decorative Fronts)

Figure 10.8   Overlap Fit Method (CFT and Martini Decorative Fronts)

Inside Fit - CFT Front
(1 Inch to 6 Inch Thick Finishing Material)

The CFT is the only approved front for inside fit applications (finish material over 1 inch thick). The CFT decorative front can be installed with or without the outer decorative front trim (included with the decorative front). See Figure 10.9.

If the desired look is to include the outer decorative front trim, finishing materials up to 1-3/16 around the fireplace opening. See Fig 10.10. For this installation, the inner decorative front hangs on four tabs located on outer decorative front trim. The auxiliary hanging brackets are not used and may be discarded. See Figure 10.11.

If the desired look is to exclude the outer decorative front trim, finishing material can be installed up to the fireplace opening. See Fig 10.12. For this installation, the inner decorative front hangs on four tabs located on the auxiliary hanging brackets. The outer decorative front trim is not used and may be discarded. See Figure 10.13.

Figure 10.10 Clearances to Appliance Opening Under Outer Decorative Front Trim

Figure 10.9 Maximum Finish Material Thickness - CFT Decorative Front

Figure 10.11 CFT Front Installation With Outer Decorative Front Trim

CFT Decorative Front
Non-Combustible Finish Material 1-6 Inches Thick

0 IN.

0 IN.

0 IN. (CFT)

Figure 10.12 Clearances to Appliance Opening <u>Without</u> Outer Decorative Front Trim

FACE OF NON-COMBUSTIBLE BOARD

(BOTH SIDES)

AUXILIARY HANGING BRACKETS

(BOTH SIDES)

Figure 10.13 CFT Front <u>Without</u> Outer Decorative Front Trim

11 Appliance Setup

A. Remove Fixed Glass Assembly

WARNING! Risk of Asphyxiation! *Handle fixed glass assembly with care. Inspect the gasket to ensure it is undamaged and inspect the glass for cracks, chips or scratches.*

- ***DO NOT*** *strike, slam or scratch glass.*
- ***DO NOT*** *operate fireplace with glass removed, cracked, broken or scratched.*
- *Replace as a complete assembly.*

Removing Fixed Glass Assembly

1. Remove the decorative front.

2. The glass assembly has two upper spring latches and two lower spring latches. See Figure 11.1. Locate the two spring latches that are on the upper left and right of the fireplace.

3. Pull upper spring latch on one side forward to release glass assembly while supporting glass assembly with opposite hand. Repeat for the other upper spring latch always taking care to support the glass assembly with one hand.

4. Grasp glass on the upper right and left sides and remove glass assembly by lifting "up" and "out".

Note: Observe the presence of a space or gap between the glass latch and the front of the appliance where the bottom of the glass assembly is positioned. This gap is designed for positive placement when replacing the glass assembly. See Section 11.I.

B. Remove the Shipping Materials

Remove shipping materials from inside or underneath the firebox.

- The splatter guard is a piece of corrugated material used to protect the appliance during the installation process before finishing work on the whole hearth is complete. Splatter guards may be factory installed or accompany the decorative front of the appliance, depending on the fireplace model. Splatter guards must be removed before appliance is fired.

- The left and right side non-combustible boards are packaged within the splatter guard. Remove them by carefully disengaging the tabs from the slots on the lower portion of the splatter guard. Install as instructed in Section 6.

WARNING! Risk of Fire! *Close the ball valve before installing the splatter guard to prevent accidental lighting. Remove the splatter guard before lighting the appliance.*

C. Clean the Appliance

Clean/vacuum any sawdust that may have accumulated inside the firebox or underneath in the control cavity.


UPPER SPRING LATCH

LOWER SPRING LATCH

GAP

Figure 11.1 Fixed Glass Assembly

D. Install the Glass Refractory (Optional)

An optional glass refractory kit is available for use with the COSMO42-IFT and COSMO32-IFT models. Install the glass refractory per instructions included with the kit.

E. Install LED Lights (Optional)

An optional LED light kit is available for use with the COSMO42-IFT and COSMO32-IFT models. Install the LED lights per the instructions included in the kit.

F. Install Media

Decorative glass media is included with the COSMO42-IFT and COSMO32-IFT models.

⚠ **WARNING**

Delayed Ignition Risk

- Place media according to instructions.
- Do NOT place media in area in front of pilot
- Do NOT place media in a position that they may fall into area in front of pilot.
- Do NOT use any media other than the Hearth & Home Technologies-supplied options for this fireplace model.

Fireplace will not function properly.
Delayed ignition may occur.

⚠ **WARNING**

Risk of Asphyxiation or Fumes.

- Place media according to instructions.
- Do NOT place media in area between glass and firebox.
- Do NOT place media in a position that they may fall into area between glass and firebox.
- Do NOT use any media other than the media supplied with this fireplace.

Fireplace will not function properly.
Gas leak may occur.

Placing the Media

Install glass media around the burner ensuring that no media is placed on the burner or in the gap located behind the burner. See Figure 11.2. Install media on top of pilot shield.


Figure 11.2 Media Placement

G. Install Stones (Optional)

An optional stones kit is available for use with the COSMO42-IFT and COSMO32-IFT models. Install the stones per instructions included with the kit.

H. Install Log Sets (Optional)

Optional log sets are available for use with the COSMO42-IFT and COSMO32-IFT models. Install the log set per instructions included with the kit.

I.   Install Fixed Glass Assembly

WARNING! Risk of Asphyxiation! Handle fixed glass assembly with care. Inspect the gasket to ensure it is undamaged and inspect the glass for cracks, chips or scratches.

- *DO NOT strike, slam or scratch glass.*
- *DO NOT operate fireplace with glass removed, cracked, broken or scratched.*
- *Replace as a complete assembly.*

Replacing Fixed Glass Assembly

The bottom glass latches have been designed to create a small gap between the glass clip and the face of the appliance. See Figure 11.1.

1. Install the bottom of the glass assembly so that the two tabs on the bottom of the glass latch engage the gap. By tilting the top of the glass towards the face of the appliance, tension will be applied to the bottom two glass latches. Use one hand to support the glass at all times.

2. Fasten the two upper glass latches, one at a time, by pulling out and downward into position on the glass assembly. Use one hand to support the glass at all times.

3. Verify that the top two glass latches are engaged by visually verifying that glass latches have engaged both left and right tabs on the glass frame.

4. Verify the bottom two glass latches have engaged the glass frame tabs by grasping the bottom of the glass frame assembly and pulling the glass frame assembly "away" from the face of the appliance and "release" the glass frame. The spring action of the clips will "pull" the glass frame assembly towards the face of the appliance if bottom clips are properly engaged. If the glass frame assembly does not pull back towards the face of the appliance, repeat steps 1-4.

WARNING! Risk of Explosion! Risk of Asphyxiation! Glass latches MUST be properly engaged. Inspect glass seal before installing decorative front. Gas could leak!

5. Reinstall decorative front.

J. Install Decorative Front

WARNING! Risk of Fire! Install ONLY decorative fronts approved by Hearth & Home Technologies. Unapproved decorative fronts could cause fireplace to overheat.

IMPORTANT! This fireplace requires an integral barrier to prevent direct contact with the hot viewing glass. DO NOT operate the fireplace with the barrier removed.

Contact your dealer or Hearth & Home Technologies if the barrier is not present or help is needed to properly install one.

For more information refer to the instructions supplied with your decorative front.

# 12 Reference Materials

A. Vent Components Diagrams

6-1/2 in.
165 mm

8-3/4 in.
222 mm

6-5/8 in.
168 mm

SLP45
45° Elbow

6-1/2 in.
165 mm

6 in.
152 mm

6-1/2 in.
165 mm

9-1/4 in.
235 mm

6-5/8 in.
168 mm

9-7/8 in.
251 mm

SLP90
90° Elbow

Effective Height/Length

Pipe	inches	mm
SLP4	4	102
SLP6	6	152
SLP12	12	305
SLP24	24	610
SLP36	36	914
SLP48	48	1219
SLP6A	2 - 6	51 - 152
SLP12A	2 - 12	51 - 305
SLP-FLEX-2	24	610
SLP-FLEX-3	36	914
SLP-FLEX-5	60	1524
SLP-FLEX-10	120	3048

Effective Height/ Length

SLP PIPE

10-7/8 in.
276 mm

8-7/8 in.
225 mm

1-1/2 in.
38 mm

SLP-HVS
Horizontal Pipe Support

8-11/16 in.
220 mm

8-11/16 in.
220 mm

1-1/2 in.
38 mm

SLP-FS
Ceiling Firestop

12 in.
305 mm

12 in.
305 mm

5-1/2 in.
146 mm

SLP-WS
Wall Shield Firestop

Figure 12.1 SLP Series Vent Components

A. Vent Components Diagrams *(continued)*

Note: Heat shields MUST overlap by a minimum of 1-1/2 in. (38 mm). The heat shield is designed to be used on a wall 4 in. to 7-1/4 in. (102 mm to 184 mm) thick. If wall thickness is less than 4 in. (102 mm) the existing heat shields must be field trimmed. If wall thickness is greater than 7-1/4 in. (184 mm) a DVP-HSM-B will be required.

SLP-TRAP
Horizontal Termination Cap

| Term Cap	Minimum Effective Length	Maximum Effective Length
Trap1	3-1/8 in.	4-3/4 in.
	79 mm	121 mm
Trap2	5-1/4 in.	9-1/4 in.
	133 mm	235 mm

SL-2DVP
Adapter

DVP-HSM-B
Extended Heat Shield

SLP-WT-BK
Wall Thimble-Black

SLP-RDS
ROOF DECK INSULATION SHIELD

Figure 12.2 SLP Series Vent Components

A. Vent Components Diagrams *(continued)*

**14 in.
356 mm**

**10-9/16 in.
269 mm**

**SLP-CCS-BK
Cathedral Ceiling
Support Box-Black**

**13 in.
330 mm**

**13 in.
330 mm**

**1-5/16 in.
34 mm**

**SLP-DCF-BK
Ceiling Firestop
Black**

**12 in.
305 mm**

**12-1/2 in.
318 mm**

**SLP-TVHW
Vertical
Termination Cap**

**14-1/16 in.
357 mm**

HOT

**14 in.
356 mm**

**7-1/2 in.
192 mm**

**10-3/4 in.
273 mm**

**SLP-FLEX-TRAP
Horizontal
Termination Kit**

**7-3/8 IN.
187 mm**

**17-7/8 IN.
454 mm**

**14 IN.
356 mm**

**6 IN.
152 mm**

**12 IN.
305 mm**

**SLP-TB1
Basement Vent Cap**

HOT↑

**10-11/16 in.
271mm**

HOT

**28-1/2 in.
724 mm**

**4-1/8 in.
105 mm**

**13-1/2 in.
343 mm**

**4-3/4 in.
121 mm**

**SLK-SNKD
Snorkel
Termination Cap**

**7-1/4 in.
(184 mm)**

**1 in.
(25 mm)**

**14 in.
(356 mm)**

3/8 in. (10 mm)

1 in. (25 mm)

**7-3/4 to 10-3/8 in.
(197 to 264 mm)**

**DVP-FBHT
Horizontal
Termination Cap
(SL-2DVP Required)**

Figure 12.3 SLP Series Vent Components

15 IN.
(381 mm)

HOT

12 IN.
(305 mm)

8 IN.
(203 mm)

SLP-HHW2
Horizontal High Wind Termination Cap

HOT

**Figure 12.4 SLP series Vent Components**

COAXIAL to COLINEAR VENTING

LINK-DV30B
**Flex Liner Kit**

768-380A
Stainless Steel Flex Pipe
(Required on COSMO32-IFT)

DV-46DVA-GCL
Coaxial/Colinear Appliance Connector

Figure 12.5 Coaxial to Colinear Vent Components

EFFECTIVE LENGTH
32 IN. (813 mm) MIN.
35 IN. (889 mm) MAX.

13-5/8 IN.
346 mm

12-1/2 IN.
318 mm

20-3/4 IN.
527 mm

PVI-SLP-B
Power Vent Inline

Optional Wire Harness	
DESCRIPTION	**PART NUMBER**
10 FT PV Wire Harness	PVI-WH10
20 FT PV Wire Harness	PVI-WH20
40 FT PV Wire Harness	PVI-WH40
60 FT PV Wire Harness	PVI-WH60
80 FT PV Wire Harness	PVI-WH80
100 FT PV Wire Harness	PVI-WH100

Note: Wire harnesses required to power the PVI-SLP-B connect to the appliance and are ordered separately from PVI-SLP-B. Contact your dealer to order.

Note: The PVI-SLP-B requires one of the following options to be installed on this appliance.
Option A: IFT-RC400 **OR**
Option B: IFT-RC150 and IFT-ACM.
These accessories are purchased separately from the PVLP-SLP. Contact your dealer to order.

Note: The PVI-SLP-B can not be installed with the Smart-Wall™ TV Kit.

16 IN.
406 mm

4-1/2 IN.
114 mm

9-3/16 IN.
(233 mm)

13-5/8 IN.
(346 mm)

16-11/16 IN.
424 mm

12-1/2 IN.
(318 mm)

15 IN.
(381 mm)

16-11/16 IN.
(424 mm)

SLP-LPC
SLP Low Profile Cap
(Approved for use with PVI-SLP-B only)

Figure 12.6   PVI-SLP-B Vent Components

A. Vent Components Diagrams *(continued)*

Top View

6-1/4 IN.
159 mm

1-1/2 IN.
38 mm

Front View

15-1/2 IN.
394 mm

14 IN.
356 mm

8 IN.
203 mm

11-1/2 IN.
292 mm

Side View

2-1/4 IN.
57 mm

4-3/4 IN.
121 mm

9-1/2 IN.
241 mm

5-1/4 IN.
135 mm

4-3/8 IN.
112 mm

10 IN.
254 mm

2-1/4 IN.
57 mm

**PVLP-SLP
Power Vent Low Profile**

Note: Wire harnesses required to power the PVLP-SLP connect to the appliance and are ordered separately from PVLP-SLP. Contact your dealer to order.

Note: A PVLP-HS heat shield is available and sold separately. Use if the PVLP-SLP is installed in a high traffic area.

Note: The PVLP-SLP requires one of the following options to be installed on this appliance.
Option A: IFT-RC400 **OR**
Option B: IFT-RC150 and IFT-ACM.
These accessories are purchased separately from the PVLP-SLP. Contact your dealer to order.

Note: The PVLP-SLP can not be installed with the Smart-Wall™ TV Kit.

**PVLP-BEK
Brick Kit**

**PVLP-HS
Heat Shield**

Required Wire Harness	
DESCRIPTION	**PART NUMBER**
10 FT PV Wire Harness	PVI-WH10
20 FT PV Wire Harness	PVI-WH20
40 FT PV Wire Harness	PVI-WH40
60 FT PV Wire Harness	PVI-WH60
80 FT PV Wire Harness	PVI-WH80
100 FT PV Wire Harness	PVI-WH100

Figure 12.7 PVLP-SLP Vent Components

B. Accessories

Install approved accessories per instructions included with accessories. Contact your dealer for a list of approved accessories.

It is recommended that optional accessories are installed prior to installation of finishing material. The lower cover panel is removable and provides access for installation of the optional fan, LED kit and remote control upgrades. If finishing material is already installed, the optional accessories must be installed by removing the basepan, burner and valve assembly. Use only Hearth & Home Technologies-approved optional accessories with this appliance.

WARNING! Risk of Fire and Electric Shock! *Use ONLY Hearth & Home Technologies-approved optional accessories with this appliance. Using non-listed accessories could result in a safety hazard and will void the warranty.*

Remote Controls, Wall Controls and Wall Switches

After a qualified service technician has installed the remote control, wall control or wall switch, follow the instructions supplied with the control installed to operate your fireplace:

For safety:

• Install a switch lock or a wall/remote control with child protection lockout feature.

• Keep remote controls out of reach of children.

Contact your dealer if you have questions.

Optional Fan

After a qualified service technician has installed the fan, follow the instructions supplied with the fan kit to operate your fan. Contact your dealer if you have questions.

Note: The optional fan can not be used with the Smart-Wall™ TV Kit.

Optional Heat Management Systems

After a qualified service technician has installed the Heat-Zone®-Gas, Smart-Wall™ TV Kit, Heat-Duct Kit, or Heat-Out-Gas Kit, follow the instructions supplied with the kit for operation. Contact your dealer if you have questions.

Note: Optional heat management systems kit must be installed while the sides of the appliance are accessible.

Note: The Smart-Wall™ TV Kit can not be used with an optional fan or Power Vent.

Optional Glass Refractory Kit

An optional glass refractory kit is available for COSMO32-IFT and COSMO42-IFT. Follow the instructions supplied with the kit for installation. Contact your dealer if you have questions.

Optional Stones Kit

An optional stones kit is available for use with the COSMO42-IFT and COSMO32-IFT models. Follow the instructions supplied with the kit for installation. Contact your dealer if you have questions.

Optional Log Kits

Traditional or Driftwood Log kits are available for COSMO32-IFT and COSMO42-IFT. Follow the instructions supplied with the kit for installation. Contact your dealer if you have questions.

Optional LED Kit

An optional LED lighting kit is available for COSMO32-IFT and COSMO42-IFT. Follow the instructions supplied with the kit for installation and operation. Contact your dealer if you have questions.